

Flows and Loads 4

		Flow litres/day		BOD grams/day		NH ₃ grams/ day	
Description	No.	Per head	TOTAL	Per head	TOTAL	Per Head	TOTAL
Industrial							
Office/ Factory without canteen	44	50	2,200	25	1,100	5	220
Amenity Sites							
Toilet (WC) per use	84	10	840	12	1,008	3	210
Shower (per use)	2	40	80	19	38	2	4
TOTAL(S) (mg/l)		FLOW	3,120	BOD	2,146	NH ₃ N	434

Breakdown of the flow data above

Office/ Location	Total Staff Numbers	Office Staff (FT)	Factory/ warehouse Staff (FT)	Agile 2 x toilet stops a day
Site without The Station House as served by septic tank under an exemption				
Transport Workshop	12	6 FT	6	0
Training Block	21	12		9
Grounds workshop	3		2	1
Highways demountable	4	2		2
Highways stores	2		2	0
Highways workman	8			8
Highways Block	19	10 FT		9
Meals on Wheels	15	3 FT		12
Building Cleaning	2	1FT		1
Total staff figures	86	34	10	42

Agile Staff – come into the depot in the morning and return late in the afternoon. Hence the 2 x toilet stops a day.