

Nolan Associates

MultiREBAR Schedule ref:

015

01

Rev.
P1

Site ref: GF Energy
Timet, Swansea

Date prepared: 08.07.15

Date revised:

Location: R.C. Details Substation Foundation

Prepared By: RW

Checked by: ARW

Job No: 2015-193

Member	Bar mark	Type & size	No of mbrs	No of bars in each	Total no	Length of each bar † mm	Shape code	A mm*	B mm*	C mm*	D mm*	E/R mm*
Wall A	01	H12	1	30	30	1550	11	500	(1050)			
	02	H12	1	28	28	1125	21	600	320	(250)		
	03	H12	1	28	28	2025	11	500	(1525)			
	04	H10	1	28	28	1100	21	300	120	(700)		
	05	H10	1	17	17	5175	00	(5175)				
	27	H12	1	28	28	1250	11	1000	(250)			
Wall B	01	H12	1	28	28	1550	11	500	(1050)			
	02	H12	1	28	28	1125	21	600	320	(250)		
	03	H12	1	28	28	2025	11	500	(1525)			
	04	H10	1	28	28	1100	21	300	120	(700)		
	05	H10	1	17	17	5175	00	(5175)				
	27	H12	1	28	28	1250	11	1000	(250)			
Wall C	01	H12	1	25	25	1550	11	500	(1050)			
	03	H12	1	23	23	2025	11	500	(1525)			
	06	H12	1	23	23	1075	21	250	270	(600)		
	21	H10	1	15	15	4150	00	(4150)				
	27	H12	1	23	23	1250	11	1000	(250)			
Wall D	01	H12	1	21	21	1550	11	500	(1050)			
	02	H12	1	24	24	1125	21	600	320	(250)		
	03	H12	1	21	21	2025	11	500	(1525)			