

Nolan Associates

MultiREBAR Schedule ref:

015

02

Rev.
P1

Site ref: GF Energy
Timet, Swansea

Date prepared: 08.07.15

Date revised:

Location: R.C. Details Substation Foundation

Prepared By: RW

Checked by: ARW

Job No: 2015-193

Member	Bar mark	Type & size	No of mbrs	No of bars in each	Total no	Length of each bar † mm	Shape code	A mm*	B mm*	C mm*	D mm*	E/R mm*
	04	H10	1	24	24	1100	21	300	120	(700)		
	07	H10	1	17	17	4225	00	(4225)				
	27	H12	1	20	20	1250	11	1000	(250)			
	22	H12	1	5	5	1900	11	400	(1505)			
	23	H12	1	5	5	2350	11	400	(1950)			
Wall E	08	H12	1	20	20	1800	11	300	(1500)			
	09	H10	1	16	16	1850	11	800	(1055)			
	10	H10	1	16	16	1250	11	200	(1055)			
	11	H10	1	16	16	1025	11	225	(800)			
	12	H10	1	10	10	1150	21	500	170	(500)		
Wall F & G	08	H12	2	24	48	1800	11	300	(1500)			
	12	H10	2	12	24	1150	21	500	170	(500)		
	13	H10	2	18	36	1125	11	900	(225)			
	14	H10	2	18	36	2200	00	(2200)				
Corners	15	H10	1	32	32	1800	11	900	(900)			
	16	H10	1	64	64	1125	11	225	(900)			
Sump	24	H10	1	16	16	1100	23	250	630	(250)		
	25	H10	1	4	4	1350	21	225	925	(225)		
	26	H10	1	8	8	2600	21	850	925	(850)		