



Improvement works on the drainage works at 2 Sisters Food Group , Llangefni

	Item	Description	Completion dates
Major works			
1	Klargester oil interceptor	Supply and installation of Klargester Oil Interceptor including 2 x surface water gullies and all associated drainage upto 40 lineal meters. Connection onto existing drain on site. To include for all removal of spoil, imported backfill, concrete and reinstatement of kerbs. Depth of excavation n.e 2.5m .	31.07.16
2	Survey structural remedials	Reference to inspection report survey findings. All works requiring urgent to short term remediation (red section) to be undertaken to specification to restore system to serviceable condition. To include the provision for specialised CIPP and patch repair systems for the installation of 11 x 225mm patch repairs. 24 x 150mm patch repairs. 9 x 100mm patch repairs including radials. 4 x isolated excavations including replacement of defective pipework. To include GPR and reports, dig permits and rams prior to digs. 1 x manhole repair to benching. and the installation of upto 5m of CIPP 150mm epoxy resin inversion liner. cost is inclusive of all materials, removal of spoil and cleaning of drain prior to works. cost to include confined space entry. gas monitoring and reporting tracing and trench support	31.07.16
3	Storage tank outlet valve	Confined space entry. Removal of current device and replacement for gate valve type. 125mm ID. Spindle to be installed above ground level requiring access port to be installed from tank to allow uninterrupted access to valve. To include civils works to excavate and install rod access port for the installation of spindle and installation of safety barriers (2" Galv steel) fixed to ground	31.07.16
4	Containment Valve	The size of valve will be based upon the modified drainage incorporating the interceptor - Supplier Aquasentry	31.07.16

R Bladon
12.02.16