

**B6.5 APPLICATION DOCUMENT REFERENCE –SG RAYNER HOMES**

**Applicant name: Taryn Rayner**

**Tel No: 07814 354 333**

**Email: taryn@sgraynerhomes.com**

**Q2. I have spoken to Peter Jones reference the application**

**Q4. Site plan enclosed, PDF version also sent to Peter Jones 9/9/19**

**Q7b. Please see enclosed report for the percolation tests. I am applying for a standard permit under the advice from Peter Jones (NRW) and Steve Underwood (Building Control) as the drainage field is just short of the British Standard to be exempt.**

PLOT A:  $7 \times 64 \times 0.20 = 89.6$  (90m<sup>2</sup>)

BS6297 guidelines converts this into a linear trench length. Using 600mm wide trenches with a 1m spacing. This equates to 150 linear metres of drainage

PLOT B:  $7 \times 57 \times 0.20 = 79.8$  (80m<sup>2</sup>)

BS6297 guidelines converts this into a linear trench length. Using 600mm wide trenches with a 1m spacing. This equates to 133.33 (135) linear metres of drainage

BS6297 is a guideline and if the linear length is not as above it is advised to speak to NRW to garner approval on what can be fitted on site.

