

HERRING BONE SYSTEM TO DISCHARGE FINAL EFFLUENT TO GROUND

Pipes to be laid at a minimum depth of 200mm.

Pipe surround to be clean shingle, gravel or grade 1 stone (20 – 50mm)

Pipes to be solid perforated foul drainage pipe with the slots at the base of the pipe laid at a uniform gradient not steeper than 1: 200

