



PERMIT

File Ref: M/75/1/5/(W)/RMM/JL

DYFED COUNTY COUNCIL
HIGHWAYS & TRANSPORTATION DEPARTMENT



OUTGOING

Statement in support of an application to establish
a landfill facility at Court House Farm, Little
Newcastle G.R. SM978289

1.0 General Description

The site as shown on the enclosed drawing numbered W/91/3/100 is required to serve the landfill requirements of my Fishguard Operational Area. The site will be used to deposit inert waste material generated from the execution of improvement and maintenance works on the highway network by my Direct Labour Organisation. The site is to the South West of the village of Little Newcastle and is in a secluded location. As you can see from the drawing the site has been used for tipping previously and this application will be for the exclusive use of the D.L.O. The types of material is shown on the enclosed schedule (numbered Appendix A).

2.0 Access

Access to the site is via the County maintained C3008 road from Letterston to Little Newcastle. The access to the facility from the above mentioned road is a locked gate, the location of which is shown on the plan. Traffic to and from the site will mainly be from the Letterston direction.

3.0 Operational Usage

The site will be in operation for a five year period and the hours of operation will be as follows:-

Monday - Thursday	08.30 - 16.30
Friday	08.30 - 15.30
Saturday	08.30 - 12 noon.

No work to be carried out on Sunday.

The level of usage will depend on the workload at any one time within the immediate operational area. It is envisaged that the maximum quantity of material to be delivered to the site in a busy week will amount to around 110 tonnes. This would involve some 12 vehicle movements per week. On the other hand there could be instances whereby the site would receive only 20 tonnes per week.

4.0 Method of Working and Restoration

The site occupies approximately 6 acres which is currently marshy wasteland and is currently not under agricultural use.

- e It is intended that the proposals be implimented in three phases as shown on the plan. Each phase will be completed prior to the

Dyfed County Council
Highways & Transportation Department

Appendix A

Schedule of Materials to be deposited resulting from typical
Highway Construction and Maintenance Works

- 1.0 Tree roots, hedgegrowth and surplus timber products.
- 2.0 Walling materials (brick concrete, or natural stone).
- 3.0 Concrete & concrete products (kerbs, paving slabs and the like).
- 4.0 As excavated natural materials.
- 5.0 Bituminous materials.
- 6.0 Crushed natural stone.
- 7.0 Highway sweepings.

LITTLE NEWCASTLE

