



FIRE PREVENTION PLAN


DOC REF: MK-E11

Mekatek Ltd
Maerdy Industrial Estate

Prepared By:
Sol Environment Ltd

Date:
September 2023

Project Ref:
SOL_23_P031_MEK

VERSION CONTROL RECORD			
Contract/Proposal Number:		SOL_23_P031_MEK	
Authors Name:		Matt Wiese	
Signature:			
Issue	Description of Status	Date	Reviewer Initials
1	First Submission to Natural Resources Wales (under reference SOL1707MK01)	September 2017	SMB
2	Second Submission to Natural Resources Wales (under reference SOL1707MK01)	December 2017	SMB
3	Third Submission to Natural Resources Wales (under reference SOL1707MK01)	December 2017	SMB
4	Fourth Submission to Natural Resources Wales (under reference SOL1707MK01)	January 2018	SMB
5	Fifth Submission to Natural Resources Wales due to permit variation	September 2023	SR
6	Sixth Submission to Natural Resources Wales due to Schedule 5	October 2024	SR

This report has been prepared by Sol Environment with all reasonable skill, care and diligence, and taking account of the Services and the Terms agreed between Sol Environment Ltd and the Client. This report is confidential to the client, and Sol Environment accepts no responsibility whatsoever to third parties to whom this report, or any part thereof, is made known, unless formally agreed by Sol Environment Ltd beforehand. Any such party relies upon the report at their own risk.

Sol Environment disclaims any responsibility to the Client and others in respect of any matters outside the agreed scope of the Services.

CONTENTS

	Page
1 Introduction	1
1.1 Introduction	1
1.2 Structure of the Fire Prevention Plan	1
1.3 Status of the Fire Prevention Plan	2
2 SITE BACKGROUND	3
2.1 Site Setting	3
3 FIRE PREVENTION PLAN	5
3.1 Control of Potential Causes of Fire	6
3.2 Preventing Self-Combustion	8
3.2.1 Managing Storage Time	8
3.3 Manage Waste Piles	9
3.3.1 Maximum Pile Sizes	9
3.4 Prevent Fire Spreading	13
3.4.1 Separation Distances	13
3.4.2 Baled Waste Storage	13
3.4.3 Fire Walls and Bays	13
3.4.4 Seasonality and Waste Stack Management	14
3.4.5 Monitor and Control Temperature	14
3.5 Detecting Fires	15
3.6 Fire Extinguishers	15
3.7 Fire Fighting Techniques	15
3.8 Fire Evacuation	16
3.9 Water Supplies	17
3.10 Managing Fire Water	17
3.11 Quarantine Area	18
3.12 During and After an Incident	18

ANNEX A: SITE PLANS

ANNEX B: DRAINAGE PLAN

ANNEX C: PROCEDURES

ANNEX D: FIRE ALARM SYSTEM

1 Introduction

1.1 Introduction

This document has been prepared by Sol Environment Ltd on the behalf of Mekatek Ltd for the operation of a waste management facility at Maerdy Industrial Estate, Rhymney.

The document provides a structured framework approach in effectively preventing potential fires associated with the processing and storage operations at the site.

This Fire Prevention Plan document (referred hereafter as the 'FPP') has been produced in accordance with Natural Resources Wales Guidance Note 16 Fire Prevention & Mitigation Plan Guidance – Waste Management (date published August 2017).

This existing approved FPP has been updated as part of a permit variation for the site which includes increasing the quantity of waste accepted on site to 50,000 tonnes per annum. Although there will be an increase in tonnage, the majority of the storage arrangements on site will remain as currently permitted due to each area having sufficient capacity for the additional waste. The only changes relate to the removal of the WEEE reception bay, the decrease in size and relocation of storage Area 1 and the decrease in size of storage Area 4.

This Fire Prevention Plan meets the fundamental objective of the FPP Guidance as it demonstrates that the site can:

- Minimise the likelihood of a fire happening;
- Aim for fire to be extinguished within 4 hours; and
- Minimise the spread of fire within the site and to neighbouring sites.

1.2 Structure of the Fire Prevention Plan

This FPP has been structured in accordance with the NRW Fire Prevention Plan Guidance and considers the following relevant aspects of the facility:

- Managing Common Causes of Fire;
 - Preventing Self Combustion;
 - Managing Waste Piles;
 - Preventing Fire Spreading;
 - Quarantine Area;
 - Detecting Fires;
 - Suppressing Fires;
 - Firefighting Techniques;
 - Water Supplies;
-

- Managing Fire Water; and
- During and after an Incident.

1.3 Status of the Fire Prevention Plan

The FPP is a “live” document and will form part of the key environmental management document for the facility. All monitoring procedures, responsibilities and compliance actions will be updated as and when required.

2 SITE BACKGROUND

2.1 Site Setting

Mekatek Ltd intend to operate a Waste Management Facility at Maerdy Industrial Estate, Rhymney. The facility will be regulated in accordance with the requirements of the Environmental Permitting Regulations, under the conditions of the Environmental Permit once determined.

As part of the permit variation, the site will accept up to 50,000 tonnes per annum of segregated waste plastics, packaging and waste electronic and electrical (WEEE) material. The site operations will consist of receiving, sorting, separating, segregating, bulking and mechanical processing mixed recyclable materials including commodities for onward treatment and / or use off site.

The daily amount of waste accepted on site varies day to day as it is dependent on what is available from suppliers however, the anticipated maximum daily amount will be 200 tonnes.

The total storage capacity on site is approximately 7,330m³.

The location of the subject Site is shown on Figure A1, Annex A, centred at approximate National Grid Reference SO 11588 06808. The proposed site layout is shown in Figure A2.

The application site is located within the south of the Maerdy Industrial Estate with industrial and commercial units to the north and west and residential dwellings of the town of Rhymney to the south and east. The site is roughly rectangular in shape and extends in area to 3ha. The site is bounded to the west by the Valley Railway Line.

The site comprises a steel frame building with tarmac, concrete and gravelled external areas. A vegetated railway siding is present to the east of the building and an old railway track and disused land in the west. The northern half of the main building is owned by Williams Medical Supplies.

The nearest residential development is located on Forge Crescent to the east and at a distance of 50m. The River Rhymey is culverted beneath the west of the site flowing north – south.

Areas of natural and unmade ground are shown on the site layout provided in Annex A.

Table 2.1 below provides information regarding the surrounding site.

Table 2.1 Site Setting	
Direction	Description
North	Immediate Vicinity: Williams Medical Supplies Within 500m: Maerdy Industrial Estate industrial units, River Rhymney Beyond 500m: Residential Area of Rhymney, School

North East	Immediate Vicinity: B4257 Within 500m: Residential Dwellings, School Beyond 500m: Agricultural land and rough terrain
East	Immediate Vicinity: Small industrial / commercial units Within 500m: B4257, Residential Dwellings, allotments, B4256 Beyond 500m: Agricultural land and rough terrain
South East	Immediate Vicinity: Houses on Wellington Way Within 500m: B4257, residential dwellings, stream with waterfall Beyond 500m: Copse, rough terrain, Tredegar & Rhymney Golf Club
South	Immediate Vicinity: Industrial units, Bungalows Within 500m: River Rhymney, B4257, Railway Line & Station, Residential Housing Beyond 500m: Residential Housing, A469, Disused Tip
South West	Immediate Vicinity: Railway, A469 Within 500m: Residential dwellings, football ground Beyond 500m: Rough terrain, Village of Pontllytyn & Fochriw
West	Immediate Vicinity: Railway Within 500m: Capital Valley Industrial Park units, A469, Rough terrain, small lake Beyond 500m: Gelligaer Common, dismantled railway, disused quarries and tips
North West	Immediate Vicinity: Railway Within 500m: Industrial Units of Maerdy Industrial Estate Beyond 500m: A469, Rough terrain, disused quarries and tips

The only environmental receptors near the site are the are the River Rhymney which runs underneath the site, a lake to the west of the site and springs to the west of the site. These are shown on the sensitive receptor plan shown in Annex A.

The Natural Resources Wales flood risk map indicates that the site lies within an area where there is a medium risk of flooding from rivers and the sea. This is land assessed as having a chance of flooding between 1 in 100 (1%) and 1 in 30 (3.3%) each year.

Although the site is not considered to be highly sensitive in terms of proximity, the facility has been designed to prevent and mitigate the offsite impacts associated with fire as far as practically possible.

The wind direction is predominantly from the south west.

3 FIRE PREVENTION PLAN

This Fire Prevention Plan has been developed to include an assessment of fire risk on site and the measures in place to prevent, detect, suppress, mitigate and contain fires.

This plan forms part of Mekatek's management system and sets out the fire prevention measures and procedures that will be put in place and used on site.

All staff and contractors working on site will understand the contents of the Fire Prevention Plan and what they must do during a fire.

The Fire Prevention Plan will be kept in the Site Office and all staff will be aware of where it is kept.

Regular exercises will be carried out to test how well the plan works and that staff understand what to do. These exercises will take place every quarter.

Please note, due to the nature of the wastes stored on site, self-combustion is considered extremely unlikely.

In accordance with the Guidance, Mekatek store the following *potentially* combustible waste materials:

- Plastics;
- Rubber; and
- Waste electrical and electronics equipment (WEEE).

However due to the nature of the materials processed there are a number of non-combustible WEEE items (i.e. large LED screens, items with combustible components removed, large metal sub-assemblies, non-combustible packaging etc), which are considered to represent a very low risk of combustion at the site.

Accordingly, the site storage areas have been segregated in accordance to combustible wastes and non-combustible wastes. Combustible waste will consist of plastics, rubber and WEEE wastes containing combustible material. Where possible non-combustible materials will be used to 'infill' and provide an effective fire break between the combustible storage bays.

All wastes will be stored within:

- Bales;
- Stillages;
- FIBC Bags; or
- Skips.

Stillages and bales will be stored no more than 4 high and the FIBC bags will be stored no more than 1 bag high or 2 bags if less than 1m³ in volume. Skips will not be stacked.

Please refer to the waste acceptance procedures provided within *Annex C – Procedures* to see the exact EWC codes accepted on site.

There is also an external storage area which is used solely for the temporary storage of recycled material or products within skip containers, before being transferred off site.

The area is purely for temporary storage before the skip is transferred off site. The external area is impermeable however it does not have sealed drainage.

The skips will be a variety of sizes however the maximum sized skip will be a 40 cubic yard skip. There will be no loose storage of processed recovered and recycled material. All skips will be single stacked.

All hazardous and WEEE processed recovered and recycled material will be stored within sealed skips. This ensures that material within them remains dry whilst also mitigating all possibility of weather ingress due to the sealed nature of the containers. Any non-hazardous processed recovered and recycled material will be stored within open skip containers.

3.1 Control of Potential Causes of Fire

The following table identifies common causes of fire and the measures that Mekatek take to reduce the risk.

Table 3.1 Control of Potential Causes of Fire		
Source of Fire	Applicability to Site and Proposed Management Controls	Residual Risk
Arson	<p>The site is currently manned between 7am – 5pm. Once operational, these hours will change, with the intention of 24/7 operation should the workload require.</p> <p>The site has secure fencing along the site boundary.</p> <p>Site access is via secured gates which will be locked during ‘out of hours’ operating times.</p> <p>Daily inspection of the site fencing and gates will be undertaken and recorded.</p> <p>The site is also equipped with CCTV monitoring.</p> <p>Any fire would be quickly identified by the sites visual inspection programme and fire detection equipment.</p>	VERY LOW
Plant and Equipment	<p>The site has a regular inspection and maintenance programme which will identify any electrical or mechanical machinery faults which could result in a machinery fire.</p>	VERY LOW

	<p>All site plant and equipment is subject to regular inspection, service and maintenance agreements in conjunction with the equipment supplier's recommendations.</p> <p>Machinery will always be parked in the dedicated plant storage area.</p> <p>All machinery is visually inspected as per FPP-E01 – Site Walkover Inspection.</p> <p>Machinery is regularly cleaned to remove any dust etc to ensure that it does not accumulate on moving parts. All machinery on site has fire suppression.</p> <p>Site vehicles are fitted with fire extinguishers with the potential for sparks regularly being monitored by site staff.</p>	
Electrical Faults Including Damaged or Exposed Electrical Cables	<p>The risk of damaged or exposed electrical cables is controlled via a regular inspection and maintenance programme.</p> <p>Any electrics on site are fully certified by a qualified electrician.</p>	VERY LOW
Discarded Smoking Materials	<p>Staff and visitors are only permitted to smoke within the designated smoking area, which is located within the car park.</p> <p>There is no smoking permitted within the operational area where waste is stored or handled.</p>	VERY LOW
Hot Works	<p>No hot works are permitted in the maintenance workshop at present without a permit to work being issued and site management being made aware of the work. The hot works will be located at a safe distance from combustible materials. The activity will be very closely managed and with the presence of a fire watchmen.</p>	VERY LOW
Industrial Heaters	<p>No industrial heaters will be used on site.</p>	N/A
Hot Exhausts	<p>The site has a regular inspection and maintenance programme which identifies any signs of a fire caused by dust settling on any hot exhausts and engine parts. This is carried via visual checks throughout the day as well as at the end of the working day.</p> <p>All inspections are carried out as per FPP-E01 – Site Walkover Inspection.</p> <p>Machinery is regularly cleaned to remove any dust, wood waste etc to ensure that this does not accumulate on moving part</p>	VERY LOW
Ignition Sources	<p>Any ignition sources on site will be kept at least 6 metres away from the stored waste on site.</p>	N/A
Leaks and Spillages of Oil and Fuels	<p>The prevention of fuels and oil leaking out from site vehicles will be achieved by the regular inspection and maintenance programme. If there are any leaks, the regular inspections allow this to be dealt with straight away.</p> <p>Spill kits will be provided throughout the site. All staff will be trained on how to use the spill kit as well as the procedures to carry out in the event of a spillage.</p>	VERY LOW

Build-up of Loose Combustible Waste and Dust	<p>The site has a regular inspection and maintenance programme which will identify any build up of wastes and dust.</p> <p>Machinery is regularly cleaned to remove any dust etc to ensure that it does not accumulate on moving parts. The site is inspected at least twice a day in accordance with the sites inspection procedure (FPP-E01). Any build up of waste and dust would be identified during the inspection.</p> <p>If any dust etc was identified then the area would be immediately cleaned (swept, blown down etc).</p> <p>Additionally, at the end of every shift the site is cleaned.</p> <p>All inspections are logged on the Site Walkover Inspection Form (Form 1 – Site Walkover Inspection). All forms are stored in the site office.</p>	VERY LOW
Reactions Between Wastes	<p>All waste is accepted on site in accordance with the sites Waste Acceptance Procedures. This ensures that no incompatible or unstable wastes will be accepted on site.</p> <p>In the unlikely event of incompatible wastes being accepted on site, wastes will be transferred to the quarantine area before removed off site.</p>	VERY LOW
Hot Loads	Mekatek do not receive hot loads.	N/A
Batteries and capacitors	<p>Any batteries and (large) capacitors within incoming waste loads will be transferred to the isolated (external) Battery Sorting Building.</p> <p>No batteries will be stored within the main building.</p>	LOW

3.2 Preventing Self-Combustion

3.2.1 Managing Storage Time

Mekatek do not accept or process any wastes which have the potential for self-heating or thermal runaway, as such self-combustion is considered extremely unlikely. The site storage areas have been segregated and designated as either 'combustible' waste or 'non-combustible' waste.

Combustible waste generally consists of plastics, rubber and WEEE wastes containing combustible material. Non-combustible waste consists of WEEE wastes containing non-combustible material (i.e. metal sub-assemblies, non-combustible packaging etc).

Mixed waste will be received on site and placed within the receipt and dispatch area, where it will be manually sorted into categories prior to being placed within the appropriate storage area.

There will be no loose piles of waste stored on site.

Although there are no risks of self combustion of the wastes, for process inventory control and plant scheduling purposes waste will be processed as soon as there are sufficient quantities to warrant a production batch (i.e. through the shredder).

Therefore:

- All waste stored within the internal general storage areas (Area 1, Area 2(a), Area 2(b), Area 3, Area 4 and Area 5) will be stored for a maximum of 3 months.
- The external wood pallet storage area will store wooden pallets for a maximum of 3 months.
- All batteries will be delivered straight to the external battery sorting building and stored within the building for a maximum of 3 months.
- The external skip storage area will store skips for a maximum of 7 days.

All storage durations on site are well within the stipulated maximum storage times within Table 1 of the NRW Guidance.

Mekatek will track all material flow through the site to ensure that the storage times specified in this plan are adhered to. All material is tracked daily and will be processed through the site on a 'first in – first out' principle.

All storage bays will be managed to ensure full stock rotation is achieved. As stated above, the wastes will be stored until there is sufficient material to warrant processing. All material will then be transferred for processing. No older material will be left within the storage area.

For all incoming waste, the location in the building and the first date when the material is added is recorded on the site waste tracking system and uploaded to the company IT system.

A twice daily review of the Fuel Storage Building and process inventory will be made by the Site Manager in accordance with procedure *FPP-E01 – Site Walkover Inspection*.

Waste will be received and accepted in accordance with the established site waste acceptance and rejection procedures which are provided within *Annex C – Procedures*. The procedures dictate that all wastes are required to be stable, non-reactive and solid in nature.

3.3 Manage Waste Piles

3.3.1 Maximum Pile Sizes

The storage arrangements on site have been designed in accordance with Natural Resources Wales Guidance Note 16 Fire Prevention & Mitigation Plan Guidance – Waste Management. Please refer to Table 3.2 below which details the storage areas on site.

Table 3.2: Waste Storage Information

Area ID	Description	Products stored in the area	Separation distance required from other internal storage areas as per guidance / Graph 2.	Comments
Area 1	Open storage 25m x 15m Maximum volume: 1,500m ³	Combustible and non-combustible wastes. Incoming material stored in stillages and bales. No loose material is stored in this area.	No separation required from Area 3 as the burn faces are separated by a concrete fire wall	<ul style="list-style-type: none"> A firewall and existing concrete block wall on the western side separates the Area 1 from Area 3. The building exterior concrete walls are on the eastern section.
Area 2	Open storage 2(a) 40m x 10m Maximum volume: 1,600m ³ 2(b) 25m x 10m Maximum volume: 1,000m ³	2(a) Combustible and non-combustible waste 2 (b) Non-combustible waste ONLY Material that has been manually liberated / sorted which is awaiting further processing or despatch. Material will be stored in bales, stillages, FIBC Bags or on pallets.	35m (available 58m) Area 2(a) and 2(b) are separated by a concrete fire wall	<ul style="list-style-type: none"> The burn face of the combustible storage Area 2(a) is 58m from the burn face of combustible storage Area 4.

Area 3	<p>Fire Bunker 25m x 5m</p> <p>Maximum volume: 500m³</p>	<p>Combustible and non-combustible waste</p> <p>Predominantly baled material and any other material awaiting further processing. If not baled the material will be stored in stillages, FIBC bags or on pallets.</p>	<p>No separation required from other internal storage areas</p>	<ul style="list-style-type: none"> 1m freeboard to be used.
Area 4	<p>Fire Bunker 19m x 10m</p> <p>Maximum volume: 760m³</p>	<p>Combustible and non-combustible waste.</p> <p>Predominantly shredded and granulated material (finished product) stored in bags.</p>	<p>10m (available 58m)</p>	<ul style="list-style-type: none"> A fire bunker wall has been constructed on the western end of storage Area 4. The southern side of the storage area is protected by an existing solid brick wall. The fire bunker walls mitigate the risk of fire to Area 5. This negates the requirement for a 31m separation distance. The burn face of the combustible storage Area 4 is 58m from the burn face of combustible storage Area 2(a). Area 2(b) stores non-combustible waste only.
Area 5	<p>Open Storage 20m x 10m</p> <p>Maximum volume: 800m³</p>	<p>Combustible and non-combustible waste.</p> <p>Mixed storage. Material will be stored in bales, stillages FIBC bags or on pallets.</p>	<p>No separation required from other internal storage areas as burn faces not directly opposite combustible storage areas.</p>	<ul style="list-style-type: none"> Concrete wall separates Area 5 and Area 4.
External Surplus Skip Area	<p>Only skip containers will be stored within this area. 25m x 10m.</p>	<p>Combustible and non-combustible processed recovered and recycled material.</p> <p>Mixed storage in skips only.</p>	<p>The storage area is located externally on an impermeable surface.</p> <p>The storage of the skips is in accordance with Section 13 of the NRW Guidance.</p>	<ul style="list-style-type: none"> A maximum of 9 x 40 cubic yard skips can be stored within this area, however it is unlikely this area will be used to full capacity. The skips will stored in a row ensuring that the skips are accessible at all times. This allows the skips to be easily removed to the quarantine area by on site equipment in the event of a fire.

	<p>Maximum volume: 270m³ (9 x 40 cubic yard skips).</p>	<p>No loose processed recovered and recycled material is stored in this area.</p> <p>Any hazardous or WEEE processed recovered and recycled material will be stored within closed skips.</p> <p>Only used for the temporary storage of skips containing recycled material or products.</p>		
Total Storage: 6,430m³				

3.4 Prevent Fire Spreading

3.4.1 Separation Distances

Area 1 is immediately opposite Area 3, therefore the separation distance requirements are applicable to these storage areas. However, this is mitigated through the use of a concrete fire wall detailed further within Section 3.4.3.

Area 4 is opposite storage area 2(a) and 2(b). Due to Area 4 being 19m long, according to Graph 2 of the Guidance, the separation distance should be 10m. The separation distance between the areas is 58m, therefore meeting the requirements of the Guidance.

Likewise, Area 2(a) is opposite Area 4. Due to Area 2(a) being 40m long, according to Graph 2 of the Guidance, the separation distance should be 36m. The separation distance between the areas is 58m, therefore meeting the requirements of the Guidance. Area 2(b) only stores non-combustible waste therefore, separation distances do not apply, however they are separated by a 58m distance.

Area 5 is across from Area 4 however this is also mitigated through the use of a concrete fire wall.

The external quarantine area with sealed drainage has a 6m separation distance.

The concrete block manufacturing area is located externally to Area 4 and 5.

3.4.2 Baled Waste Storage

Although some wastes are stored within bales, due to the types of waste (non self-heating) stored on site, monitoring is not considered necessary.

Examples of waste stored in bales are:

- Cardboard;
- Plastic;
- Electrical Waste e.g. circuit boards and cable.

Baled waste will be stored for a maximum of 3 months on site, which is well within the stipulated maximum storage times stipulated within Table 1 of the Guidance.

Bales will not be stored more than 4m high. As far as practically possible, bales will be stacked in a manner that avoids the potential of energetic air-flows between the bales.

3.4.3 Fire Walls and Bays

As detailed within Table 3.2, Area 3 which will store combustible and non-combustible wastes is a concrete fire bunker. The fire bunker is constructed of grout sealed 'Legio' block fire walls, ensuring a

1m freeboard at all times. The walls will offer a fire resistance period of at least 120 minutes. The western side of Area 1 is separated from Area 3 via the fire bunker walls negating the need for a separation distance between the two areas.

The southern side of Area 4 is protected from Area 5 by an existing solid brick wall. This mitigated the risk of fire to Area 1 and Area 5 negating the need for a separation distance between the two areas.

Area 2(a) and Area 2(b) are separated by a concrete fire wall with a 1m freeboard.

The other fire walls relate to the temporary storage bunkers. These walls are also constructed of sealed 'Legio' blocks. Waste will only be stored in these for a maximum of 1 day.

Mekatek will keep records of the material stored within the storage areas to ensure that not storage times are exceeded. All material is tracked daily and will be processed through the site on a 'first in – first out' principle.

Due to the storage arrangements and the nature of the wastes stored on site, temperature monitoring is not considered necessary. Additionally, no wastes will be stored for longer than 3 months.

In the event of a hotspot / fire being detected, as long as it is safe to do so, the bale / stillage / bag would be removed to the external bunded quarantine area where it would be cooled.

A trained site operative will carry out a visual inspection twice daily in accordance with *Procedure FPP-E01 – Site Walkover Inspection* to ensure that all areas are being managed correctly and in line with the Fire Prevention Plan.

3.4.4 Seasonality and Waste Stack Management

The materials stored on site are not subject to seasonal variation.

Mekatek will track all material flow through the site to ensure that the storage times specified in this plan are adhered to. All material is tracked daily and will be processed through the site on a 'first in – first out' principle.

3.4.5 Monitor and Control Temperature

Due to the nature of the wastes being stored and the fact that no wastes are stored for longer than 3 months, temperature monitoring is not considered necessary.

There will be no loose piles of waste stored on site.

If waste is processed through the waste processing equipment, all waste will be cool before transferring to a storage area.

A trained site operative will carry out a visual inspection on site twice daily in accordance with *Procedure FPP-E01 – Site Walkover Inspection* to ensure that the Processing Building is being managed correctly.

Due to the storage arrangements, turning of waste is not considered necessary.

3.5 Detecting Fires

The building is equipped with a UKAS accredited fire detection system (smoke and heat detection) supplied by Chubb Fire & Security Ltd. The system consists of 118 detectors and 13 manual call points. The system is monitored by Chubb who in the event of a fire being detected, will call the Site Manager. If the Site Manager is no available then Chubb will immediately call the fire service.

The system will be tested and inspected in accordance with BS5839-1:2013, BS EN 54-2:1997+A1:2006, BS EN 54-3:2001, BS EN 54:1998, BS EN 54-5:2001, BS EN 54-7:2001, BS EN 54-11:2001, BS EN 54-13:2005, BS EN54-23:2010.

Any fires on site would be immediately identified. In the event of a fire, a member of staff will immediately raise the alarm and then contact the emergency services.

A trained site operative will carry out a visual inspection on site twice daily in accordance with *Procedure FPP-E01 – Site Walkover Inspection* to ensure that the Processing Building is being managed correctly and that all detection systems are working correctly.

The automatic fire detection system provides 24/7 detection of the building. This allows a fire to be detected quickly.

Please refer to *Annex D – Fire Alarm Systems* for further information on detecting fires.

3.6 Fire Extinguishers

Although waste is stored within a building, the nature of the operations on site and the general low risk combustibility of the waste types stored, a suppression system is not considered necessary.

There is a sufficient number of fire extinguishers located throughout the premises which are all mounted on wall brackets. A fire extinguisher schedule is kept on file to ensure that all extinguishers are regularly inspected.

3.7 Fire Fighting Techniques

The site has been designed in order to allow active firefighting.

An off-site emergency information pack is provided in a box on the main gate into the site and contains emergency contact numbers, a site plan and copy of this FPP.

The fire access route shown on the site plan will be inspected as part of the site walkover inspections to ensure that safe access to the site for fire and rescue services and other emergency responders is always achieved. In the event that anything is blocking the route, it will be immediately flagged to the Site Manager and removed.

Additionally, the area around the site perimeter will be kept clear at all times to ensure the site is always accessible by the fire service, as demonstrated on the site plan. The site perimeter will also be checked as part of the site walkover inspections.

The site has an alternative access point, the entrance of which is accessed via the adjacent Williams Medical Services site. This access point will remain clear at all time and also be checked as part of the site walkover inspections.

Upon identifying or being made aware of a fire, the site manager will raise the alarm, alert all present on site to the fire and its location and alert emergency services.

The site will be evacuated in accordance with the site evacuation plan with exception of those staff involved in active fire fighting.

All staff, contractors and visitors would follow the Fire Evacuation procedure as included in Section 3.10 below.

Staff will only tackle the fire using the fire extinguishers if it is safe to do so. If not safe to do so, staff are to await the Fire and Rescue Service (FRS), who would then take the appropriate actions.

All personnel working on site will be provided training in the Fire Prevention Plan and all associated procedures and controls.

The FPP training will be provided to all new starters and temporary employees working at the site.

FPP refresher training will be carried out to all personnel at least annually.

3.8 Fire Evacuation

The assembly point is located opposite the weighbridge and is clearly signposted. The assembly point is clearly shown on the site plan provided within Annex A.

Sites rules are reinforced via use of fire drills and planned response scenarios.

All personnel to follow the instructions of the Fire Wardens and the Site Manager.

A list of trained Fire Wardens is maintained and displayed on the site, together with a list of on call staff to attend the site in the event of a fire outside of normal operation hours.

The Fire Evacuation Procedure is provided to staff, contractors and visitors which states:

- On discovery of a fire, immediately operate the fire alarm by pressing the nearest break glass call point and / or contact the Site Manager via a radio to ensure the alarm is raised;
- Fire Wardens and staff must only tackle the fire if they are trained to do so, the equipment is appropriate and if their safety or that of others is not compromised.
- Leave the building / work area by the nearest available exit / safe route and report directly to the assembly point located opposite the weighbridge.
- Leave quickly but in a calm, controlled and orderly manner. Do not detour to collect personal items;
- Do not re-enter the building / work area for any reason until authorisation has been given by the Site Manager / Fire Brigade.
- The Site Manager will assess the situation and call the Fire and rescue Service if required.

This document is reviewed and updated annually, or sooner if required. The document details all hazards and the control measures that are in place and / or required to prevent fires.

3.9 Water Supplies

There are four on-site mains fed Fire Hydrants as shown on the site plan provided within *Annex A – Site Plan*.

These fire hydrants are connected to a mains water supply and would provide a continuous supply of water in the event of a fire.

All hydrants are easily accessible for the fire service.

3.10 Managing Fire Water

In the event of a fire, all firewater will drain to the firewater holding bund which will be isolated from the surface water drainage system via a penstock valve. Company tankers would be mobilised from the Mekatek site in Carmarthen (1-hour mobilisation time) to remove the firewater held in the bay either in the event that more firewater storage was required, or after a fire to dispose of the firewater.

The bund has a capacity of 245m³.

Fire water runoff is directed to the holding bund due to the fall of the building.

The penstock valve prevents run-off from leaving the building and soaking to ground, as it ensures that all firewater is contained within the drainage system.

As mentioned above, the fire water will be removed via tanker from the on-site surface water drainage system which will transport the water offsite to an appropriate treatment facility.

The external storage area has a separate fire water containment system. In the event of a skip catching fire within the external storage area, drain blockers will be used to block the surrounding drains. Due to surfacing being impermeable and the fall of the land, the area has a capacity of 24m³. In the event that more firewater storage was required, tankers would remove the firewater. Tankers would also be used to dispose of the firewater after a fire.

3.11 Quarantine Area

The site is equipped with an external quarantine area with a dedicated sealed drainage system.

The quarantine area has been designed to hold 900m³ (15m x 15m x 4m) which will easily hold 50% of the largest storage area on site.

The location of the quarantine area is identified on the site plan provided within *Annex A – Site Plan*.

3.12 During and After an Incident

During an Incident

During any fire fighting or subsequent clear up operations, any incoming wastes will be diverted to an alternative waste processing site.

In the event of a fire that may impact the sensitive receptors, the following action plan has been developed:

- The site will have a mobile tannoy on site. This will be used to alert nearby residents / businesses that there is a fire on site and that there is the potential need for evacuation;
- As well as this, trained site operatives will knock on residents' doors surrounding the site to ensure that they are aware of the fire. The site operatives will start at the nearest residential receptors on Wellington Way.

The use of the tannoy and knocking on peoples' doors ensures that all nearby residents will be made aware of the fire on site.

After an Incident


The site will be thoroughly cleaned after an incident. Any charred / partially combusted / combustion products will be disposed of an appropriate facility. It is anticipated that the clearing of combusted material will not take long, as the company are confident that any fires will be appropriately controlled and therefore will not result in significant volumes of burnt waste.

All fire water will be captured by the drainage system and transferred off site via tanker and appropriately disposed of.

All equipment will be checked for any fire damage. In the event that any equipment has been damaged, it will be removed from site and fixed / replaced as soon as possible.

This ensures that the impact to the community, infrastructure and the environment is minimal.

ANNEX A: SITE PLANS



1. Do not scale off this drawing
2. All dimensions to be confirmed on site
3. This drawing is copyright of Sol Environment Ltd
4. This drawing is to be read in conjunction with relevant consultant drawings and specifications

Rev: 1
Date: SEPT 23
Desc: Original

Client: MEKATEK LTD
Project: RHYMNEY
Drawing Title: SITE LOCATION


Job No: SOL_23_P031_MEK
Date: SEPT 23
Drawn By: SOPHIE RAINEY


Drawing No: MK01
Revision: 1
Scale: NTS



Sol Environment Ltd
Unit 5.3 Paintworks
Bristol, BS4 3EH

t: +44(0)1684 572727
e: enquiries@sol-environment.co.uk
www.sol-environment.co.uk






Receptor No.	Receptor Name
R1	Residential Receptor
R2	Ysgol Y Lawnt (Primary School)
R3	Redwood Memorial Hospital
R4	Bryn Awel Primary School
R5	Pontlloftyn Primary School
R6	Rhymney Comprehensive School
R7	Valley Railway Line
R8	Rhymney Bus & Train Station
R9	Integrated Health & Social Care Centre
R10	RFC & Sports Ground
R11	Care Home (Min-Y-Mynydd)
R12	Sports Ground
R14	Capital Valley Industrial Park
R15	The Lawns Industrial Estate
R16	Tredagar & Rhymney Golf Club
R17	A469
R18	A4257
R19	Heads of the Valleys Industrial Estate
R20	Valley Manor Nursing Home
ER1	River Rhymney
ER2	Lake
ER3	Springs

1. Do not scale off this drawing 2. All dimensions to be confirmed on site 3. This drawing is copyright of Sol Environment Ltd 4. This drawing is to be read in conjunction with relevant consultant drawings and specifications	Rev:	Date:	Desc:	Client:	MEKATEK LTD	Job No:	SOL1707MK01	Drawing No:	MK05
	0	AUG 17	Original	Project:	MAERDY INDUSTRIAL ESTATE	Date:	AUG 17	Revision:	0
				Drawing Title:	FIRE PREVENTION PLAN SITE PLAN	Drawn By:	SOPHIE PERRIN	Scale:	NTS

ANNEX B: DRAINAGE PLAN



MEKATEK, UNIT C,
MAERDY INDUSTRIAL ESTATE,
RHYMNEY, NP22 5PY

**DRAINAGE STRATEGY
(VERSION 1)**

SCALE 1 : 1000 @ A3

MARCH 2017 DRAWING NO: DL/ECOTEC/001A

ANNEX C: PROCEDURES

This procedure is linked to Form 1 – Site Walkover Inspection

This Site Walkover Inspection Procedure must be carried out at least twice a day.

Machinery Inspection

It is the responsibility of the **Site Manager** to ensure that the following controls are adhered to.

1. All machinery is visually checked at least twice a day.
2. If any dust etc has accumulated on the machinery, the machinery will be cleaned immediately.
3. Additionally, at the end of every shift all machinery is thoroughly cleaned.
4. Any sign of maintenance required must be recorded on Form 1 and dealt with immediately.
5. Any signs of a fire caused by dust settling on any hot exhausts / engine parts would be identified immediately, however due to the regular visual inception and cleaning programme this is very unlikely to happen.
6. All visual inspections are recorded using Form 1.
7. The completed Site Walkover Inspection Form will be handed on to the next shift staff or security staff as appropriate. The Site Manager will inspect and file all completed forms every 24 hours.

Electrical Faults

8. During the visual inspection of appropriate electrical cables must be inspected to identify if any are damaged or exposed.
9. All visual inspections are recorded using Form 1.
10. The completed Site Walkover Inspection Form will be handed on to the next shift staff or security staff as appropriate. The Site Manager will inspect and file all completed forms every 24 hours.

Waste Storage Inspection

11. The waste storage areas will be visually checked at least twice a day.
12. The areas must be inspected along each length to enable a full 360 degree inspection.
13. All visual inspections are recorded using Form 1.
14. Any blindspots / hard to observe locations must also be inspected, as long as it safe to do so.

DATE: September 2023
REVISION: 2
DOC #: FPP-E01
PAGE: 2 of 2

FIRE PLAN PROCEDURE Site Walkover Inspection



15. The completed Site Walkover Inspection Form will be handed on to the next shift staff or security staff as appropriate. The Site Manager will inspect and file all completed forms every 24 hours.

High Risk Observations – immediate action required

16. The following high risk observations should be recorded and actioned immediately. **All incidents noted in a) to e) below must be notified to Site Manager immediately. In the event of fire or smoke, the local Fire & Rescue Service must also be contacted immediately.**

- a) Any fires on site, small or large scale, isolated, controlled or otherwise;
- b) Any evidence of any high temperature materials (i.e. evidence of steam or smoke) from any aspect of the storage area;
- c) Any storage areas not managed in accordance with the FPP must be dealt with accordingly;
- d) Any evidence of any signs of potential vandalism or attempted vandalism (discarded materials, accelerants etc; evidence of tampering with plant and equipment);
- e) Any evidence of non-Mekatek personnel / trespassers on the site at any time; and
- f) Any signs of any spillage.

Low Risk Observations

- a) Any mobile plant not parked within the plant storage area;
- b) Any dust etc accumulated on any machinery; and
- c) Any obvious damage to a boundary fence, site security equipment or company processing equipment.

Author / Function or Department:

Process Owner / Department:
Site Manager

UNCONTROLLED WHEN PRINTED - MASTER COPIES HELD IN SITE OFFICE

DATE: September 2023
REVISION: 2
DOC #: Form 1
PAGE: 1 of 2

FIRE PLAN PROCEDURE
FORM 1
Site Walkover Inspection



Site Name		Date / Time	
Name of Person Undertaking Inspection			

Please refer to FPP-E01 – Site Walkover Inspection

Please identify what machinery / aspects of the site have been inspected, at what time and if any remedial actions carried out (e.g cleaning, maintenance):

Any evidence of external fire / vandalism, machinery or equipment fault or malfunction must be instantly reported.

Please illustrate what storage areas have been inspected and at what time:

Any evidence of self heating / self ignition, external fire / vandalism, machinery or equipment fault or malfunction must be instantly reported.

Storage / Pile Ref.	Identified Problem
AREA 1	
AREA 2	
AREA 3	
AREA 4	

Author / Function or Department:

Process Owner / Department:
Site Manager

UNCONTROLLED WHEN PRINTED - MASTER COPIES HELD IN SITE OFFICE

DATE: September 2023
REVISION: 2
DOC #: Form 1
PAGE: 2 of 2

FIRE PLAN PROCEDURE
FORM 1
Site Walkover Inspection



AREA 5	
SURPLUS SKIP AREA	

Notes / Action required *(to address unsatisfactory conditions)*

Form reviewed by: (PRINT
Name)

Job
Title

Author / Function or Department:

Process Owner / Department:
Site Manager

UNCONTROLLED WHEN PRINTED - MASTER COPIES HELD IN SITE OFFICE

ANNEX D: DETECTION AND SUPPRESSION INFORMATION

Chubb Fire & Security Limited
Tel: 0344 879 1666
www.chubb.co.uk

PPW 2681893

Schedule

25 MAY 2016



Account and Location No.

A								->					
P								->					

Customer Name:	ECO TECHNOLOGY LTD	Contact name:	
Contact name:	Mr Paul Meller	Site address:	
Invoice address:	Head office, Block C Moredun Ind Est, Rhymney		
Postcode:	NP22 5PY	Postcode:	
Tel:	07971030922	Tel:	

SAME AS
INVOICE

Prevent Fire

Chubb offers a range of Fire Risk Assessments.

Mover's Agreement

Date _____

25/5/2016

Detect Fire

First visit:

Charge per annum

Charge / Visit

Contract No.

Fire detection system:	Visits / Year: 4	JUNE / 2016	£ 863.96	£ 215.99						
Fire detection system size:	Panels: 2	Detectors: 110	Call points: 15							
FireCARE monitoring:	Please refer to the FireCARE contract									

Contain Fire

Contain Fire	No.	Visits / Year	First Visit	Charge / Each/Visit	Minimum Service charge	Gold 1:	Gold 2:
Portable fire extinguishers:	21	1	Aug 16	£ 7.13 /visit	£ 55.40	Gold 3:	Gold 4: ✓
					Call Out charge		
					£		

No. of portable fire extinguishers: Powder: 7 CO2: 6 Foam: 1 Water/Additives: 6 + 1 Other:

	No.	Visits / Year	First Visit	Charge / Each/Visit	Minimum Service charge	
Wheeled fire extinguishers:			/ 200	£ : /visit	£ :	Contract No.
Fire Blankets:			/ 200	£ : /visit	£ :	

Mechanical (Inc Hose Reels, Dry Riser etc)	Please refer to the Mechanical Contract
--	---

	No. of System	No. of Cylinders	Type of System	Visit/Year	First Visit	Charge / Each/Visit	Contract No.
Gaseous suppression system: (Electrical Element)					/ 200	£	

Escape Fire

Escape Fire	No. of lights	No. of Visits/Year	First Visit	Charge / Each/Visit	Contract No.
Emergency lights :			/ 200	£ :	




Purchase Order No required. Yes ☐ No ☒ Required either Purchase Order No. or Customer Signature

Prices shown are exclusive of VAT, which will be charged in addition

Minimum Term 2 Years

Special service instructions:

70% Discount on new supply
Any Extras must be first authorized by
MK Paul Mellor - 07971030922

Print Customer name	Job Title	SIGNED for and on behalf of the Customer	Date
PAUL MELLOR	DIRECTOR		250516
Print Representative's Name	ID Number	Representative's Signature	Date
PAUL GLETTON	692		250516
		SIGNED for on behalf of Chubb Fire & Security Limited	Contract Date
			270516