

MONITOR CONTRACT ORDER

Contractor	Contract Ref:	Area:	Engineers Ref:	Risk Score:	Monitor Ref:
MGR	WAL/MGR/4799	Towy	2295368, 2295366	9	0450_WAL_MGR

Location Details

ELR	Structure Type	Structure No	Mileage	OS Ref	Local name
LLA	Culvert	2 61.5	2.1353		3'6" brick arch with tidal flap

Order Details

Date Issued	Response Time	Project No / Task No	Payment In Installments	Lump Sum (if applicable)
02/06/2025 13:14:07	52 Week	187161 - 6.2.1 TOWY	No	Not Applicable
Payment Periods	Liquidated Damages	Liquidated Damages Amount	Commencement	Period for completion of works
As per 13 Railway Periods	Not Applicable	Not Applicable	02/06/2025 13:14:07	01/06/2026 13:14:07

Other Details / Requirements

Scheme Drawing	No	Form 3	No	Design Only	No	Hand Over	No
Work Package Plans and Task Briefings	No	Form 4	No	As Built Drawing	No	Hand Back	No
Physical Works Estimate Required	No	Form 5	No	PCIP Required	No	Report Required	No
Form 1	No	Form 6	No	Site Manager	Stephanie Dyson		
Form 2	No	Form 7	No	Works Delivery Manager			

Work Remit:

Work Location On Structure

Work Defect

Work Details

(1) Review the condition of flap valve framing including missing bolts. If possible repair the frame and ensure a water tight seal is formed. If required replace flap with a standard FRP tidal flap in line with manufactures guidance and environmental consents. Review the condition of the timber lintel the framing connects too, at the scoping stage. (2) Rake out and repoint joints and reinstate loose and missing masonry. Note: Marine license requirement.

Work Quantification

Possession Requirements

Contractor to arrange where required

Notes

Design Requirements : No

Please note the requirements of the contract that a Risk Assessment must be carried out and a Work Package Plan with Task Briefings produced and approved/accepted in accordance with Network Rail company standards, prior to the commencement of work

Contractor to assess the impact on track stability of the works and carry out appropriate dilapidation survey and monitoring regime where applicable

CDM Regulations: The Contractor must advise the Network Rail project manager if the works are deemed to be notifiable.

[\(Last updated 09/09/2015\)](#)