

Please provide a description of all mitigation measures proposed to avoid any impact on designated conservation sites.

To prevent polluting materials entering water environment:

- Biodegradable oil to be used in mobile plant and vehicles.
- No polluting materials will be stored within 10m of the watercourse
- Working areas will be kept clean and litter free
- Spill kit materials and booms will be available
- All equipment and mobile tower scaffold will be removed from the works location at the end of each shift.
- Any debris from timber removal will be contained in polypropylene durable bags and removed from the work site at the end of each shift.
- All cleared materials will be taken from site by registered waste carrier
- A Permit to Work in a Watercourse will be completed daily
- ECAMP (Environmental Contingency & Accident Management Plan) will be in place