



**REVIEW OF ENVIRONMENTAL MONITORING
RESULTS AT THE
NANT-Y-GWYDDON LANDFILL SITE DURING THE
PERIOD JAN 25 – DEC 25**

**Amgen Rhondda Ltd.
Bryn Pica Landfill Site
Llwydcoed
Aberdare
CF44 0BX**

**Phone: 01685 870770
Fax: 01685 874684**

Executive Summary

Amgen Rhondda Ltd. has carried out a review of the results of environmental monitoring activities undertaken at the Nant-y-Gwyddon landfill site, during 2025.

The submission to the Natural Resources Wales (NRW) of a periodic review of environmental monitoring results is required under Section 7.4 of the site Environmental Permit (EP). It is outlined in this document that such a review should include:

- a) An analysis and review of the environmental monitoring results recorded for the site under these conditions, with an interpretation of the trend of the results against background and trigger level and reference standards;*
- b) A review of a risk assessment for the site, taking account of the findings under (a).*

The purpose of this report is to review the environmental performance of the Nant-y-Gwyddon Landfill over the previous 12 months and to fulfil the above requirement of Section 7.4 of the site EP.

The 2025 monitoring results continue the long-term trend observed over recent years, indicating stable environmental conditions with no evidence of significant impacts to surrounding groundwater, surface water or landfill gas receptors.

TABLE OF CONTENTS

1. INTRODUCTION	1
1.1 TERMS OF REFERENCE AND CONTEXT	1
1.2 SCOPE OF WORKS	1
2. SITE DESCRIPTION	1
2.1 SITE LOCATION AND SURROUNDINGS	1
2.2 SITE MANAGEMENT AND ENGINEERING	2
3. LEACHATE, GROUNDWATER AND SURFACE WATER	5
3.1 ANALYSIS SUITES	5
3.2 LEACHATE	6
3.3 SURFACE WATER	10
3.4 GROUNDWATER	16
4. LANDFILL GAS	21
4.1 OVERVIEW	21
4.2 RISK ASSESSMENT	21
4.3 MONITORING RESULTS	22
5. CONCLUSIONS	24
5.1 OVERVIEW	24
5.2 LANDFILL LEACHATE LEVELS AND CONTAMINATION	24
5.3 SURFACE WATER QUALITY	24
5.4 GROUNDWATER QUALITY	25
5.5 SUB-SURFACE LANDFILL GAS MONITORING	25
6. RECOMMENDATIONS	25

APPENDICES

Appendix A - Drawings

Drawing No.	Title
ARL2026/ENV/01/001	SITE LOCATION PLAN
ARL2026/ENV/01/002	GENERAL LAYOUT
ARL2026/ENV/01/003	LEACHATE MANAGEMENT AND MONITORING
ARL2026/ENV/01/004	SURFACE WATER MONITORING POINTS
ARL2026/ENV/01/005	GROUNDWATER MONITORING
ARL2026/ENV/01/006	LANDFILL GAS MANAGEMENT AND MONITORING

Appendix B - AGREED MONITORING SUITES AS PER THE WORKING PLAN.

Appendix C - TIME SERIES PLOTS ILLUSTRATING THE RESULTS OF ARL's LAB ANALYSIS OF LEACHATE SAMPLED AT THE NANT-Y-GWYDDON LANDFILL SITE DURING THE PERIOD JAN 15 – DEC 25.

Appendix D - TIME SERIES PLOTS ILLUSTRATING THE RESULTS OF ARL's LAB ANALYSIS OF SURFACE WATER SAMPLED AT THE NANT-Y-GWYDDON LANDFILL SITE DURING THE PERIOD JAN 15 – DEC 25.

Appendix E - TIME SERIES PLOTS ILLUSTRATING THE RESULTS OF ARL'S LAB ANALYSIS OF GROUNDWATER SAMPLED AT THE NANT-Y-GWYDDON LANDFILL SITE DURING THE PERIOD JAN 15 – DEC 25.

List of Tables

Table No.	Title
3.1	ARL's implementation of the required chemical analysis suites for leachate, groundwater and surface water monitoring at Nant-y-Gwyddon during the period Jan 25 – Dec 25.
3.2	Result of Leachate Level Monitoring carried out at the Nant-y-Gwyddon Landfill Site, Jan 25 – Dec 25.
3.3	Annual average concentrations of the principal leachate contaminants monitored by Amgen Rhondda Ltd at the Nant-y-Gwyddon landfill site during the period Jan 25 - Dec 25, compared with those national averages reported in DoE Research Report No. CWM 072/94 (DoE 1995).
3.4	Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2025.
3.5	Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2024.
3.6	Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2023.
3.7	Specification of groundwater monitoring boreholes situated at the Nant-y-Gwyddon Landfill Site.
3.8	Summary of Trigger and Control Levels currently in place at the Nant-y-Gwyddon Landfill Site.
3.9	Summary of groundwater monitoring results recorded at the Nant-y-Gwyddon Landfill Site during the period Jan 25 – Dec 25, compared with the approved Trigger and Control levels for the site.
4.1	Summary of sub-surface landfill gas monitoring undertaken by ARL at the Nant-y-Gwyddon Landfill during the period Jan 25 – Dec 25.

REVIEW OF ENVIRONMENTAL MONITORING AT THE NANT-Y-GWYDDON LANDFILL SITE, GELLI, RHONDDA.

1. INTRODUCTION

1.1 Terms of Reference and Context

As the Environmental Permit (EP) holder for the Nant-y-Gwyddon Landfill Site (Gelli, Rhondda Cynon Taff), Amgen Rhondda Ltd. (ARL) has continued Environmental Monitoring at the site in accordance with the conditions of the EP and procedures documented in the approved working plan.

This report provides an analysis and review of the environmental monitoring results recorded during the period Jan-25 to Dec-25, with an interpretation of the trends of the results against site specific trigger levels and other relevant reference standards.

An updated Hydrogeological Risk Assessment (HRA) was completed in June 2007 for the site, as part of the assessment process for definitive closure. This was approved in March 2008, permitting the site to enter into 'definitive closure' in accordance with the Landfill Regulations (England and Wales) 2002. The HRA provides a model for ground conditions at the site and has been used to interpret the results of monitoring carried out by ARL staff.

1.2 Scope

This document uses the description of the site's HRA to interpret the results of monitoring implemented and recorded at the Nant-y-Gwyddon Landfill Site by ARL. It covers the following items:

- Leachate Level and Composition
- Surface Water Quality
- Groundwater Level and Quality
- Landfill Gas Monitoring

2. SITE DESCRIPTION

2.1 Site Location and Surroundings

The Nant-y-Gwyddon site is located at Ordnance Survey National Grid Reference (NGR) SS 980 940, in an elevated position above the Rhondda Fawr valley, as shown on the Site Location Plan (Dwg. No. ARL2026/ENV/01/001).

The landfill site has been established in what was a naturally developed depression at the head of the valley formed by the Nant-y-Gwyddon stream. The base of the site is at an approximate elevation of 320 mAOD, whereas the elevation of the upper surface of the current landform is approximately 350 mAOD.

North of the landfill site, Myndd-y-Gelli descends steeply towards the small village of Gelli. The Hen Dr'er ring and platform cairns are located just outside the vicinity of the landfill in this direction. These are listed Bronze Age Ancient Monuments.

In an easterly direction, Llwynypia Mountain consists of gently sloping rough grazing land passing, down slope, into the natural woodland of the Glyn-Cornal nature reserve and Craig-Pont-Rhondda, both of which are designated SSSI (Special Site of Scientific Interest).

The elevated land to the south and west of the landfill is predominantly Forestry Commission plantation. However, these forested areas also extend down the south-facing slopes of Clydach Vale.

Clydach Vale (Grid Reference 2980 1930) is the closest built-up area to the site; the Clydach Vale Rugby Club being the closest property, less than 1000 m away from the southern margin of the landfill site.

Coal Tip No. 232 is situated adjacent to the site entrance, at the top of the site access road. This was, along with the smaller No. 233 tip, constructed from waste produced by the Gelli Colliery. However, all of the latter and part of the former have now been removed, having been used for site preparation and ongoing operational purposes (i.e. daily cover, landfill cap engineering).

2.2 Site Management and Engineering

The Nant-y-Gwyddon Landfill Site was designed and operated as a containment Landfill and consists of a management infrastructure for the control and disposal of contaminated water (leachate) and landfill gas.

Waste disposal operations at Nant-y-Gwyddon were split into Phase 1, now containing approximately 1.25 million tonnes of landfill waste and Phase 2. Despite the construction of an engineered barrier system (basal liner) over the 3 hectare area of Phase 2, no waste has been deposited within this phase, due to the early closure of the site in March 2002.

The landfill site boundary comprises an area of approximately 24 ha which can be described as follows:

- **Phase 1 Landfill** – Containing approximately 1.25 million m³ of waste in an area of approximately 9 ha. This area has now been fully remediated with the construction of an engineered geocomposite capping layer and drainage measures.
- **Phase 2** – The 3.5 ha area historically referred to as Phase 2, previously consisted of an engineered barrier system (basal liner) and leachate storage facility. These have now been removed and the restored area now consists of gently sloping grassland and a small surface water lagoon and associated drainage. In 2023, a partnership between Rhondda Cynon Taf Council, Amgen Rhondda and renewable energy developer Infinte Renewables resulted in the construction and commission of a 2.3 MW single wind turbine with the this area.
- **Site Offices, Weighbridge, Car Park and Landfill Gas Compound** – These are located adjacent to the site entrance. Further information related to the landfill gas compound is provided below.

Leachate Management

Landfill waste deposited in the Phase 1 area is contained by the presence of a basal engineered barrier (basal liner) and leachate drainage system.

As detailed in the Site's Working Plan Document this consists of the following:

- 300 mm graded colliery spoil, with leachate collector drains (in no fines granular surrounds and geotextile wrap), placed on
- 2.5 mm HDPE Geomembrane, placed on
- 300 mm graded colliery spoil with sub liner drainage (as above), placed on
- Compacted colliery spoil sub-grade, placed on
- Excavated and re-compacted ground.

The completed phase 1 area is now fully capped with an engineered (permanent) landfill cap. Since its completion in September 2005, the cap been shown to be successful in acting as a barrier to infiltration and thus significantly reducing the volume of leachate produced at the site.

The permanent cap covers the entire area of the landfill and is tied into the basal liner at the margins of the landfill, thus completing containment engineering. The cap consists of the following elements as referenced in the approved validation report for the works:

- 750 mm restoration soils, placed upon
- 300 mm colliery spoil protection layer (nominal particle size 20 mm), placed upon
- 6 mm non-woven Geosynthetic drainage layer and subsurface collector drains, placed upon
- 1 mm LLDPE Geomembrane fully welded and tested, placed upon
- 6 mm non-woven Geosynthetic drainage layer and subsurface collector drains, placed upon
- 200 mm cap foundation layer (nominal particle size 20 mm), placed on
- graded / regularised landfill surface.

In addition to the above the following active leachate extraction measures are present at the site:

- A fixed pumping station, situated at the base of the landfill western flank (an area previously referred to as Jones's Bund).

Leachate collected from the site's basal drainage and active pumping systems are piped to a large concrete holding tank located in the eastern area of the site. From this location, leachate is discharged untreated to the foul sewer network via a dedicated 1.5 km underground pipeline.

This discharge is done in accordance with a Consent to Discharge (No. AN00117), as provided and regulated by the water authority (Dwr Cymru / Welsh Water).

Landfill Gas Management

Landfill gas (LFG) production at Nant-y-Gwyddon is controlled using active gas extraction and flaring.

This consists of the following elements:

- Geo-synthetic gas drainage layer and pipe-work (underneath the plastic cap).
- 40 no. vertical landfill gas extraction wells
- Collection pipe-work connected to 4 no. control manifolds and dewatering knockout pots.
- Gas extraction plant (100 m³/hr capacity) and high temperature enclosed landfill gas flare.

3. LEACHATE, GROUNDWATER AND SURFACE WATER.

3.1 Leachate, Groundwater and Surface Water Analysis Suites.

The Nant-y-Gwyddon Landfill Site – Working Plan (Amgen Rhondda Ltd., August 2001, updated 2008) outlines the manner in which leachate, groundwater and surface water samples are obtained from the site along with a specified suite of chemical analysis for each of these groups.

Laboratory analysis for a range of water chemistry determinands are required on a monthly, quarterly and annual frequency depending on their presence within leachate contamination, and general association with wastes deposited at the site, and their relative cost of analysis, along with the logistics involved in accurately quantifying their presence.

Analysis of water samples obtained from the site are undertaken by an independent laboratory services company. Throughout 2025 ARL has used third party analytical services provided by Envirolab Ltd (www.envlab.co.uk).

Tables 10, 11 and 12 from the working plan detail the analysis required for leachate, groundwater and surface water monitoring. These have been reproduced in appendix B of this document for reference. The timetable via which ARL implemented these analysis suites on leachate, groundwater and surface water is illustrated in Table 1 below.

Table 3.1: ARL's implementation of the required chemical analysis suites for leachate, groundwater and surface water monitoring at Nant-y-Gwyddon during the period Jan 25 – Dec 25.

2025 – Leachate Analysis												
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Analysis Suite	Mon	Qtr	Mon	Mon	Qtr	Mon	Ann	Mon	Mon	Mon	Qtr	Mon
Date of Monitoring	28/01	18/02	11/03	08/04	06/05	07/06	01/07	05/08	02/09	08/10	04/11	02/12
2025 – Groundwater Analysis												
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Analysis Suite	Mon	Qtr	Mon	Mon	Qtr	Mon	Ann	Mon	Mon	Mon	Qtr	Mon
Date of Monitoring	29/01	25/02	19/03	23/04	20/05	18/06	16/07	12/08	16/09	14/10	25/11	09/12
2025 – Surface Water Analysis												
	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Analysis Suite	Mon	Qtr	Mon	Mon	Qtr	Mon	Ann	Mon	Mon	Mon	Qtr	Mon
Date of Monitoring	28/01	18/02	11/03	08/04	06/05	03/06	01/07	05/08	02/09	01/10	04/11	02/12

Note:

Mon - Monthly Analysis Suite
 Qtr - Quarterly Analysis Suite
 Ann - Annual Analysis Suite

3.2 Leachate

ARL carries out monthly monitoring of leachate level and contamination concentrations at the Nant-y-Gwyddon Landfill Site. Two sampling locations are provided for leachate to be collected directly from the landfill waste and a third, external to the waste, for the monitoring of leachate quality prior to disposal.

Leachate Level Monitoring

Leachate level monitoring is carried out monthly, involving dip measurement, undertaken by a suitably qualified landfill technician. The location of the 2 monitoring points currently used is illustrated in Drawing No. ARL2026/ENV/01/003 and a description provided below:

- **L5a (leachate inspection manhole L5a)** – L5a is a leachate inspection chamber located within the landfill immediately adjacent to the Inert Bund retaining the eastern margin of the waste. This chamber is linked directly to the basal drainage system, at a location considered to be the lowest point in the landfill. Leachate collected by the basal drainage system flows to this point under the influence of gravity - prior to exiting the landfill via an underground pipeline.

Over the previous 12 months only a small flow of leachate has been noticeable at this location, with technicians unable to take sample on occasions during prolonged periods of dry weather.

- **LPS1 (Leachate Pumping Station, Western Flank)** – As part of the remediation works a leachate extraction sump was constructed in the area previously referred to as Jones Bund. Historically this area was subject to significant leachate build-up, sourced by run-off from the, as then uncapped Phase 1 landfill area and the un-tipped Phase 2 area. This installation extends to the base of the landfill and can be used to interpret the head of water present within the waste at this location.

The results of leachate level monitoring carried out throughout 2025 are provided in Table 3.2 (overleaf). Results from 2024 are also illustrated in order to demonstrate any longer term trends.

Table 3.2: Result of Leachate Level Monitoring carried out at the Nant-y-Gwyddon Landfill Site, Jan 24 – Dec 25.

Date	L5a		LPS1	
	Depth of Installation (m bgl)	Water Head (m)	Depth of Installation (m bgl)	Water Head (m)
Jan-24	20	0 (dry)	6.9	0.73
Feb-24	20	0 (dry)	6.9	0.7
Mar-24	20	0 (dry)	6.9	0.68
Apr-24	20	0 (dry)	6.9	N/R
May-24	20	0 (dry)	6.9	N/R
Jun-24	20	0 (dry)	6.9	N/R
Jul-24	20	0 (dry)	6.9	0.78
Aug-24	20	0 (dry)	6.9	0.81
Sep-24	20	0 (dry)	6.9	0.78
Oct-24	20	0 (dry)	6.9	1.368
Nov-24	20	0 (dry)	6.9	0.736
Dec-24	20	0 (dry)	6.9	0.85
Jan-25	20	0 (dry)	6.9	0.79
Feb-25	20	0 (dry)	6.9	0.634
Mar-25	20	0 (dry)	6.9	0.84
Apr-25	20	0 (dry)	6.9	0.84
May-25	20	0 (dry)	6.9	0.83
Jun-25	20	0 (dry)	6.9	0.73
Jul-25	20	0 (dry)	6.9	0.85
Aug-25	20	0 (dry)	6.9	0.86
Sep-25	20	0 (dry)	6.9	0.75
Oct-25	20	0 (dry)	6.9	0.74
Nov-25	20	0 (dry)	6.9	0.68
Dec-25	20	0 (dry)	6.9	0.82

L5a

Monthly monitoring of Leachate Inspection Chamber L5a has shown it to be consistently dry over the previous 12 months. This observation has been confirmed by visual inspection of the installation. A very small basal flow is observed within the drainage channel and this is freely escaping the landfill (under gravity) into the external leachate management pipe-work.

This gives good indication that there is little or no head of leachate acting on the basal lining system in this area of the landfill. L5a is connected to a network of drains that cover a large area of the Phase 1 landfill.

LPS1

Leachate levels in this area of the landfill are shown to have been less than 1m throughout 2025, averaging 0.84 m and thus are compliant with the permit requirements for the site.

Leachate Quality Monitoring

Leachate monitoring and sampling is undertaken at 3 locations at the site. The location of these monitoring points is illustrated in Drawing No. ARL2026/ENV/01/003 and a description provided below:

- **L5a (leachate inspection manhole L5a)** – Leachate sampled at this location is sourced directly from the waste. It is thought to be the most representative monitoring location for leachate generated directly within the waste mass. On visual inspection there is a small basal flow of leachate draining under gravity, but this cannot be sampled using the existing sample methodology.

In order to gain some meaningful data from this location an alternative sample point has been constructed at a location approximately 100 m down-gradient of the landfill site. This consists of an inspection chamber which has been modified to allow ARL's Technical Staff to gain access (for sampling) to the basal flow identified within the L5a Leachate Chamber.

- **LPS 1 (Leachate Pumping Station, Western Flank)** – Leachate sampled at this location is sourced directly from the waste. Previously, leachate samples were taken from the leachate attenuation lagoons (LL01). However, this has ceased due to the removal of this infrastructure during restoration works undertaken in 2006.
- **L5 (leachate holding tank)** – Prior to disposal (to foul sewer), leachate from the landfill is stored within the leachate holding tank. This regulates the discharge of leachate (trade effluent) to the foul sewer at a maximum rate of 6 l/s.

Table 3.3 (overleaf) provides a comparison of the results of leachate monitoring at the Nant-y-Gwyddon Landfill Site during the period Jan-23 to Dec-25.

Table 3.3: Annual average concentration of the principal leachate contaminants monitored by Amgen Rhondda Ltd at the Nant-y-Gwyddon landfill site during the period Jan 23 - Dec 25, compared with those national averages reported in DoE Research Report No. CWM 072/94 (DoE 1995).

Determinant	DoE (1995)	L5a			L5			LPS1		
		2023	2024	2025	2023	2024	2025	2023	2024	2025
Alkalinity	5,376	312	274	299	176	N/R	13.4	197	207	207
NH₄ as N	889	0.1	0.17	0.5	5.5	N/R	0.4	11.3	13.0	10.7
Conductivity	11,502	633	589	582	475	N/R	281	431	500	496
496BOD	374	0.5	0.16	8.4	1.7	N/R	1.5	0.3	1.4	0.9
COD	2,307	3.4	13.3	8.0	10.7	N/R	13.5	15.3	20.1	17.7
Cadmium	0.015	N/D	N/D	N/D	N/D	N/R	N/R	N/D	N/D	N/D
Chloride	2,074	34.0	24.7	23.2	24.0	N/R	8.5	34.7	41.0	36.4
Chromium	0.09	N/D	N/D	N/D	N/D	N/R	N/R	N/D	N/D	N/D
Iron	27.4	0.008	0.011	0.011	0.058	N/R	0.047	2.2	1.0	1.0
Lead	0.2	N/D	N/D	0.0001	N/D	N/R	N/D	N/D	N/D	N/D
pH	7.52	7.8	7.9	7.6	7.5	N/R	7.8	7.2	7.1	6.9
Potassium	854	10.5	12.7	7.4	N/R	N/R	3.8	18.3	14.3	20.2
Sodium	1,480	13.5	17.7	8.2	10.0	N/R	6.1	29.3	20.5	34.7
Sulphate	67	42.0	34.0	38.0	29.0	N/R	19.0	33.3	24.8	43.8
TON	0.86 – 1.0345	1.7	4.9	2.4	3.3	N/R	1.5	1.0	0.9	1.6

Note: All values in mg/l except Conductivity (uS/cm³).
N/D – Not Detected in any samples analysed.

Leachate sampled at the Nant-y-Gwyddon Landfill site over the previous three years is shown to be weak in nature (dilute) when compared to the national averages reported in DoE Research Report No. CWM 072/94 (DoE 1995). Of particular interest are the low levels of Ammoniacal Nitrogen (NH₄ as N), Chloride and Electrical Conductivity. Annual averages for these parameters are significantly below the national average presented above. Taking this into consideration, along with the overall volume of leachate still being collected at the site, suggests that the site's leachate management system continues to intercept groundwater beneath the site.

There does not appear to be any trend in the strength of leachate samples at the site. Concentrations of the principal leachate contaminants have remained relatively consistent over the referenced monitoring period.

3.3 Surface Water

Background

The Site is located near the watershed separating the Rhondda Fawr and Clydach valleys. Therefore, no part of the Site is within the EA's Indicative Floodplain for the Rhondda Fawr.

(see <http://www.environment-agency.gov.uk/maps/info/floodmaps/>).

This part of the Rhondda valley receives a high annual rainfall (the long-term average annual total precipitation for the Site is over 1500 mm), most of which leaves the surface water catchment, via a network of tributary rivers and streams, in the Avon Rhondda Fawr (which typically exhibits a high intensity-short duration response to rainfall events).

The Nant-y-Gwyddon stream (a small tributary of the Afon Rhondda Fawr) is fed by clean surface water drainage from within the area of the licensed landfill.

It has been shown that a large proportion of the groundwater passing beneath the Nant-y-Gwyddon site enters into the Nant-y-Gwyddon stream via a number of springs located on the valley side. These are typically associated with the outcrop location of the No. 1 Rhondda and No. 1 Rhondda Rider coal seams – the main aquaclude retaining groundwater beneath the site.

Under the EA's General Quality Assessment (GQA) Scheme, the water quality of the Afon Rhondda Fawr, in common with all surface water features designated as "Main River" across all of England and Wales, is regularly monitored and annual targets for improvement set (where necessary).

Previously, the adjacent reach of the Afon Rhondda Fawr has been generally classified as Grade A (the highest possible rating). It is fair to note that, since this classification has been the same at points both upstream and downstream of its confluence with the Nant-y-Gwyddon stream, the impact of the latter is clearly insignificant, in terms of both quantity and quality.

Surface Water Monitoring

ARL currently monitor the quality of surface water at six locations on and around the Nant-y-Gwyddon Landfill Site. The location of these points is illustrated in Drawing No. ARL2026/ENV/01/004 (Appendix A) and a description provided below:

Surface water monitoring points **SW1**, **SW5** and **SW6** are within the immediate vicinity of the landfill site and located along the Nant-y-Gwyddon stream:

- **SW5** (settlement lagoon in Phase 2 area) – Previously the monitoring location SW 5 referred to the water sampled from the site fire lagoon. The fire lagoon was removed during the 2005 / 2006 remediation work and the monitoring point has now been relocated to the settlement lagoon situated in the restored Phase 2 area.
- **SW6** (upper Nant-y-Gwyddon stream) - The majority of the surface water collected from the area surrounding the landfill is discharged into the stream at this point. Site drainage discharge at this location is covered by a Consent to Discharge Surface Water (EA Ref: AN0308201) as regulated by Natural Resources Wales. This sample point is typically dry and has not yielded a sample through this reporting period.

- **SW1** (lower Nant-y-Gwyddon) - Flow rates are increased due to groundwater input from streams at, or above, this point.

In addition, there are three more distant surface water monitoring points (**SW2**, **SW3**, and **SW4**), which are located as follows:

- **SW4** (Glyncornel Nature Reserve Lake) – Located just upstream of the lake in a small spring. Tracer tests have shown that 80% of the groundwater passing below the landfill emerges on the lower slopes of the Rhondda Fawr Valley, some of which feed into this lake.
- **SW2** (Nant-y-Clydach Fach) – This stream flows in a south-easterly direction through the Clydach Vale Country Park and is also fed by groundwater thought to originate beneath the site.
- **SW3** (Cwm Cae Dafydd Tributary) – This tributary originates on the south-western margin of the landfill site boundary, flows south through the village of Cwm Clydach, and into the Nant Clydach (a major tributary of the Rhondda Avon Fawr).

Surface Water Quality

Annual averages have been calculated for the main surface water quality determinands monitored at the site by Amgen during the period January 2023 to December 2025. This analysis has been summarised, below, in Tables 3.4, 3.5 and 3.6 for 2025, 2024 and 2023 respectively. The identity and value of the chosen EAL is indicated for each determinand, with any exceedances highlighted in **bold** type.

Table 3.4: Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2025.

Water Quality Determinand	Units	EAL		Surface Water Monitoring Point					
				SW 1	SW 2	SW 3	SW 4	SW 5	SW6
Alkalinity (as CaCO ₃)	mg/l	-	-	81	N/D	44.3	50.4	61.3	Dry
Ammonia (NH ₄ as N)	mg/l	DWS	0.5	0.06	<0.03	N/D	<0.03	<0.03	Dry
BOD	mg/l			0.6	0.13	0.33	0.33	0.17	Dry
Cadmium	mg/l	DWS	0.005	N/D	N/D	N/D	N/D	N/D	Dry
Calcium	mg/l	DWS	250	17.4	3.2	13.9	13.6	16.9	Dry
Chloride	mg/l	DWS	250	6.6	7.3	7.4	8.1	5.6	Dry
Chromium	mg/l	DWS	0.05	N/D	N/D	N/D	N/D	N/D	Dry
COD	mg/l	-	-	3.1	3.2	2.7	2.5	13.8	Dry
Copper	mg/l	DWS	2	N/D	N/D	N/D	N/D	N/D	Dry
EC @ 20°C	µS/cm	DWS	1500	231	51	149	152	140	Dry
Iron	mg/l	EQS	1	0.013	0.031	0.025	0.015	0.282	Dry
Lead	mg/l	DWS	0.01	0.0003	0.0002	<0.0001	<0.0001	N/D	Dry
Magnesium	mg/l	DWS	50	15.2	1.5	8.5	9.5	9.7	Dry
Nickel	mg/l	DWS	0.02	N/D	N/D	0.001	N/D	N/D	Dry
Nitrate (as NO ₃)	mg/l	DWS	50	1.6	0.7	0.6	1.2	N/D	Dry
Nitrite (as NO ₂)	mg/l	DWS	0.1	N/D	N/D	N/D	N/D	N/D	Dry
pH	-	DWS	5.5-9.5	7.8	6.8	7.4	7.6	7.0	Dry
Potassium	mg/l			5.1	N/D	1.0	0.6	2.7	Dry
Sodium	mg/l	DWS	200	6.6	4.1	5.0	5.8	4.9	Dry
Sulphate	mg/l	DWS	250	37.5	5.5	26.3	22.3	9.0	Dry
Zinc	mg/l	DWS	5	0.0003	0.0095	0.0045	0.010	0.004	Dry

N/D - Substance not detected above minimum reporting value.

Table 3.5: Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2024.

Water Quality Determinand	Units	EAL		Surface Water Monitoring Point					
				SW1	SW2	SW3	SW4	SW5	SW6
Alkalinity (as CaCO ₃)	mg/l	-	-	71.3	4.9	24.3	42.7	55.2	Dry
Ammonia (NH ₄ as N)	mg/l	DWS	0.5	<0.03	<0.03	0.75	0.04	<0.03	Dry
BOD	mg/l			0.17	0.40	0.17	0.50	0.44	Dry
Cadmium	mg/l	DWS	0.005	N/D	N/D	N/D	N/D	N/D	Dry
Calcium	mg/l	DWS	250	15.3	2.0	11.8	12.0	16.5	Dry
Chloride	mg/l	DWS	250	4.5	6.6	5.3	5.4	6.1	Dry
Chromium	mg/l	DWS	0.05	N/D	N/D	N/D	N/D	N/D	Dry
COD	mg/l	-	-	4.9	4.7	4.8	51.4	13.4	Dry
Copper	mg/l	DWS	2	N/D	N/D	0.001	N/D	N/D	Dry
EC @ 20°C	µS/cm	DWS	1500	195	55	122	137	144	Dry
Iron	mg/l	EQS	1	0.018	0.030	0.035	0.003	0.143	Dry
Lead	mg/l	DWS	0.01	N/D	N/D	N/D	N/D	N/D	Dry
Magnesium	mg/l	DWS	50	13.8	0.67	7.3	7.8	8.3	Dry
Nickel	mg/l	DWS	0.02	N/D	N/D	0.001	N/D	<0.001	Dry
Nitrate (as NO ₃)	mg/l	DWS	50	1.3	2.0	0.5	1.1	N/D	Dry
Nitrite (as NO ₂)	mg/l	DWS	0.1	N/D	N/D	N/D	N/D	N/D	Dry
pH	-	DWS	5.5-9.5	7.7	6.9	7.3	7.4	7.1	Dry
Potassium	mg/l			6.0	N/D	2.0	2.3	2.8	Dry
Sodium	mg/l	DWS	200	6.5	3.7	4.8	6.0	4.5	Dry
Sulphate	mg/l	DWS	250	32.3	6.3	21.3	14.8	18.8	Dry
Zinc	mg/l	DWS	5	0.003	0.009	0.008	0.005	4.3	Dry

N/D - Substance not detected above minimum reporting value.

Table 3.6: Annual Averages for Surface Water Quality Determinands monitored at Nant-y-Gwyddon in 2023.

Water Quality Determinand	Units	EAL		Surface Water Monitoring Point					
				SW1	SW2	SW3	SW4	SW5	SW6
Alkalinity (as CaCO ₃)	mg/l	-	-	81.3	3.0	43.9	44.9	78.2	Dry
Ammonia (NH ₄ as N)	mg/l	DWS	0.5	0.1	0.3	0.1	0.0	0.1	Dry
BOD	mg/l			0.27	0.43	0.18	0.36	2.0	Dry
Cadmium	mg/l	DWS	0.005	0.0005	0.0001	0.0005	0.0005	0.0001	Dry
Calcium	mg/l	DWS	250	20.5	2.0	16.3	13.3	18.3	Dry
Chloride	mg/l	DWS	250	5.4	6.9	7.0	6.8	3.4	Dry
Chromium	mg/l	DWS	0.05	0.0003	0.0005	0.0003	0.0003	0.0003	Dry
COD	mg/l	-	-	8.8	22.5	7.5	79.9	17.6	Dry
Copper	mg/l	DWS	2	0.0001	0.0002	0.0038	0.0026	0.010	Dry
EC @ 20°C	µS/cm	DWS	1500	407	57	165	161	174	Dry
Iron	mg/l	EQS	1	0.02	0.02	0.04	0.003	0.438	Dry
Lead	mg/l	DWS	0.01	0.0003	0.0005	0.0003	0.0003	0.0003	Dry
Magnesium	mg/l	DWS	50	18.3	1.0	10.0	9.3	9.3	Dry
Nickel	mg/l	DWS	0.02	0.0001	0.0001	0.0005	0.0008	0.0005	Dry
Nitrate (as NO ₃)	mg/l	DWS	50	1.18	0.6	0.4	0.68	0.03	Dry
Nitrite (as NO ₂)	mg/l	DWS	0.1	0.03	0.05	0.03	0.03	0.03	Dry
pH	-	DWS	5.5-9.5	7.9	7.3	7.5	7.6	7.2	Dry
Potassium	mg/l			7.0	0.5	2.3	2.3	3.8	Dry
Sodium	mg/l	DWS	200	7.5	4.5	5.5	6.0	4.8	Dry
Sulphate	mg/l	DWS	250	49.8	8.5	35.0	22.0	7.0	Dry
TOC	mg/l	-	-	0.67	2.00	0.67	1.3	2.9	Dry
Zinc	mg/l	DWS	5	0.014	0.001	0.001	0.006	0.004	Dry

N/D - Substance not detected above minimum reporting value.

Summary of Surface Water Monitoring Results

Surface water sampled within the four main watercourses surrounding the Nant-y-Gwyddon site is considered to be of a good quality. Table 3.6 (previous) presents annual average concentrations, calculated for 22 key Water quality determinands and compares them to water quality thresholds (e.g. Drinking Water Standards – DWS).

Of the 22 water quality determinands presented, it can be seen that there was no exceedances of any water quality standard, when considering the annual averages calculated for 2025. This was also the case for annual averages calculated for surface water monitoring results recorded during the 2024 and 2023 calendar years. The consistency of these observations indicate that surface water monitored on and around the Nant-y-Gwyddon Landfill Site continue to be of good quality.

Further analysis is provided below:

General Water Quality Determinands

Throughout 2025, it is noted that concentrations of ammoniacal nitrogen (ammonia NH_4 as N) were very low, averaging less than 0.3 mg/l at each of the 6 surface water monitoring locations. Of the 56 water samples analysed for NH_4 as N, a total of 8 (14%) returned a positive result above the minimum reporting value of 0.05 mg/l NH_4 as N. The maximum value recorded during 2025 was 0.5 mg/l, recorded at SW 1 in Nov-25.

Other relevant observations are as follows:

- Chloride concentrations are consistently low, averaging less than 15 mg/l for each of the surface water monitoring locations (compared to the UK Drinking Water Standard of 250 mg/l).
- Measurements of Electrical Conductivity (EC) taken at each of the 6 monitoring locations were low, averaging between 50 – 500 $\mu\text{S}/\text{cm}^3$ throughout 2025. This is well within the UK-DWS of 2500 $\mu\text{S}/\text{cm}^3$.
- Nitrate concentrations in the streams surrounding the Nant-y-Gwyddon Landfill Site were consistently low in all samples monitored in 2023, averaging between 0.5 and 1.5 mg/l.

Dangerous Substances

Surface Water samples taken from the site and the surrounding area during 2025 have been subject to a number of independent analyses, for a range of chemical substances considered to be harmful to human health and the environment (Dangerous Substances). This analysis has been undertaken on a quarterly and annual basis and the results reviewed by ARL Staff.

The main substances of concern when considering the potential impact of landfill leachate on the water environment are considered to be as follows:

- Benzene
- Cadmium
- Mercury

1,2 Dichloroethane is a further substance that was previously detected in leachate samples at the Nant-y-Gwyddon Landfill Site and has therefore been analysed on a frequent basis. The following paragraphs provide a summary of the results of the above substances recorded in surface water samples taken on and around the Nant-y-Gwyddon Landfill Site during the period Jan-25 to Dec-25:

- Throughout 2025 a total of 5 surface water samples were analysed for the presence of Benzene. There was no indication of Benzene in any of the 4 samples (above the MRV of 0.1 µg/l).
- A total of 18 surface water samples taken at Nant-y-Gwyddon in 2025 were analysed for the presence of Cadmium. There was no positive detection of Cadmium in any of the samples (above the MRV of 0.0002 mg/l).
- A total of 5 surface water samples taken at Nant-y-Gwyddon in 2025 were analysed for the presence of Mercury. There was no positive detection of Mercury in any of the samples (at or above the MRV of 0.0001 mg/l).
- Of the 18 surface water samples analysed for 1,2 Dichloroethane throughout 2025, no positive values were reported. This gives a good indication that this substance was not present above the Minimum Reporting Value (MRV) of 0.0002 mg/l.

Summary

Amgen Rhondda Ltd. has continued monitoring the quality of surface water on and around the Nant-y-Gwyddon landfill in accordance with the site's environmental permission. Throughout 2025, a total of 58 samples were taken from 5 'off-site' and 1 'on-site' monitoring location. The quality of water sampled on each of these occasions was within the UK Drinking Water Standards listed in table 3.6.

It is concluded that the surface water on and around the Nant-y-Gwyddon Landfill Site is of good quality. There is no indication that the landfill is having a determinable impact on the surface water environment surrounding the site.

3.4 GROUNDWATER

Background

The area of land on which the Nant-y-Gwyddon Landfill Site is located is designated as being underlain by a Minor Aquifer (as per the EA's Policy and Practice for the Protection of Groundwater (1998)) and is covered by soils with a low leaching potential.

Based on the information available on the EA's website, it has been determined that the Site is not within the source protection zone (SPZ) or any abstraction license for public water supply. However, there is a licensed abstraction within 1 km of the Site, held by Welsh Water (Dwr Cymru), which relates to two points on the Nant Cesig stream, less than 1200 metres to the north-west of the perimeter of the landfill. Although these points are not currently used for supply, the licenses remain in force and, as such, they are afforded all the statutory protection that such a licence entails.

The local Environmental Health Department has confirmed that there are no known private (domestic) water supplies for individual properties, or groups of properties, within the vicinity of the Site, except for that at Bwllfa Farm (NGR SS 9704 9415).

The Hydrogeological conceptual site model derived for Nant-y-Gwyddon, identifies two groundwater bodies beneath the landfill site that could be at risk from any fugitive emissions of leachate from the Site. These have been identified as follows:

- The Upper Aquifer – Previous investigations have indicated seasonal groundwater retained above a siltstone / mudstone aquiclude located approximately 25 to 30m above the No.1 RR coal seam.
- The Main Aquifer – Groundwater retained above the No.1 RR coal seam (and associated argillaceous horizons), between 28 and 35 metres below the base of the landfill. Various springs located at the level of the outcrop of the No.1 RR coal seam (eastern slope of Myndd-y-Gelli / Llywnypia Mountain) are thought to represent the discharge points for this aquifer, issuing into various surface water receptors.

Groundwater Monitoring

The Nant-y-Gwyddon site is equipped with a total of 8 functional groundwater monitoring boreholes. The site has a number of historic installations that do not yield groundwater for sampling and have been adopted as part of the subsurface gas monitoring program. Monitoring is carried out on a monthly frequency for both level and water quality. Independent laboratory analysis is undertaken in accordance with those schedules listed in Appendix B.

The location of each of these groundwater monitoring points is illustrated in Drawing No. ARL2026/ENV/01/005 and an overview of their specification provided in Table 3.7 (overleaf).

Table 3.7: Specification of 8 groundwater monitoring boreholes situated at the Nant-y-Gwyddon Landfill Site.

BH ID	Location	Co-Ordinates		
		East	North	Depth
NG 105	Up-gradient	297719	193376	15.0
NG 106		297659	193831	14.4
NG 107		297660	193896	8.4
GW 94		297674	194008	29.1
NG 104	Down-gradient	298146	193946	15.0
GW 6		297931	193765	43.0
NG 101		298030	194230	34.5
GW 10		297931	193946	15.0

Trigger Levels

As part of the process of completing 'Definitive Closure' for the Nant-y-Gwyddon Landfill Site, a series of site specific Trigger Levels for groundwater quality were agreed with the Environment Agency (now NRW). This was completed in March 2008 in accordance with the EA's Technical Guidance Document LFTGN01.

This document states:

'Generally, trigger levels should be set for the same substances that are considered in the risk assessment, particularly where those substances are present in the highest concentrations in leachate and are most mobile in the sub-surface.'

'As a general rule, trigger levels should be set for at least three, but no more than ten substances'.

Table 3.8 (below) illustrates the agreed trigger levels and their associated compliance checks in groundwater situated around the landfill. In addition to this, control levels are used as check points, so that any deterioration in groundwater quality, towards the trigger level, can be identified at an early stage.

Table 3.8: Summary of Trigger and Control Levels currently in place at the Nant-y-Gwyddon Landfill Site.

Water Quality Determinand	Units	Trigger Level	Control Level 1	Control Level 2
List I:				
Benzene	ug/l	0.1	n/a	n/a
Cadmium	ug/l	0.5	n/a	n/a
Mercury	ug/l	0.1	n/a	n/a
List II:				
Ammonia (NH ₃ as N)	mg/l	0.50	0.24	0.33
Chloride	mg/l	50	17	28
Nickel	mg/l	0.050	0.017	0.028
Zinc	mg/l	0.043	0.024	0.030

3.9: Summary of groundwater monitoring results recorded at the Nant-y-Gwyddon Landfill Site during the period Jan 25 – Dec 25, compared with the approved Trigger and Control levels for the site.

		List 1			List II			
		Benzene	Cadmium	Mercury	Ammonium (NH4 as N)	Chloride	Nickel	Zinc
GW 6	Samples	4	4	1	12	12	4	4
	Control 1	0	0	0	1	6	0	0
	Control 2	0	0	0	1	0	0	0
	Trigger Level	0	0	0	1	0	0	0
NG 101	Samples	2	2	N/R	10	10	2	2
	Control 1	0	0	N/R	0	0	0	0
	Control 2	0	0	N/R	0	0	0	0
	Trigger Level	0	0	N/R	0	0	0	0
NG104	Samples	4	4	1	12	12	4	4
	Control 1	0	0	0	0	0	0	0
	Control 2	0	0	0	0	0	0	0
	Trigger Level	0	0	0	0	0	0	0
GW 10	Samples	4	4	1	11	11	4	4
	Control 1	0	0	0	1	0	0	0
	Control 2	0	0	0	1	0	0	0
	Trigger Level	0	0	0	0	0	0	0

List I Substance – Benzene

Of the 14 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, and GW 10, Benzene was not detected in any of the samples sent for analysis. Therefore no exceedances of the Benzene trigger level occurred at the landfill site, during the 12 month period Jan-25 to Dec-25.

List I Substance – Cadmium

Of the 14 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, and GW 10, Cadmium was not detected in any of the samples sent for analysis (at or above MRV of 0.0002mg/l). Therefore no exceedances of the Cadmium trigger level occurred at the Nant-y-Gwyddon Landfill during the 12 month period Jan-25 to Dec-25.

List I Substance – Mercury

There was no detection of Mercury of any of the groundwater samples taken at Nant-y-Gwyddon during the period Jan-25 to Dec-25. There was no recorded exceedance of the trigger level.

List II Substance – Ammonia (NH₄ as N)

Of the 45 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, GW 10, there was a single exceedance of the trigger levels for Ammonia (NH₄ as N). A value of 0.65 mg/l was reported for GW6 in a sample obtained in Nov-25. This was an isolated occurrence and is not thought to represent leachate contamination. Of the 12 samples taken from GW 6 during 2025, NH₄ as N concentrations in 7 samples were reported to be below the minimum reporting value of 0.05mg/l. The annual average for 2025 is calculated as being 0.10 mg/l which is significantly below the threshold.

List II Substance – Chloride

Of the 45 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, GW 10, there was no exceedances of the trigger levels (i.e. 50 mg/l), when considering the analysis reported for chloride. The maximum value reported for groundwater samples taken down-gradient of the landfill, during the referenced monitoring period was 26.0 mg/l (within down-gradient borehole GW 6, sampled in May-25).

These observations further support the above statement, that leachate present within the landfill at Nant-y-Gwyddon is not having a demonstrable impact on groundwater at the site.

List II Substance – Nickel

Of the 14 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, GW 10, there was no exceedances of the trigger levels (i.e. 0.05 mg/l), when considering the analysis reported for nickel. Furthermore, there was no exceedances of either control level 1 or 2 (i.e. 0.017mg/l and 0.028 mg/l, respectively).

List II Substance – Zinc

Of the 14 groundwater samples taken from down-gradient boreholes GW6, NG101, NG104, GW 10 during the reporting period, there was not a single exceedance of the agreed trigger level of 0.043 mg/l for Zinc. Furthermore, there was no exceedances of either control level 1 or 2 (i.e. 0.024 mg/l and 0.030 mg/l, respectively).

4. LANDFILL GAS.

4.1 Overview.

ARL currently uses 13 ground monitoring borehole installations for the purpose of detecting any potential migration of landfill gas (LFG) from the base of the Nant-y-Gwyddon landfill. The location of these installations in relation to the landfill is illustrated on Drawing No. ARL2026/ENV/01/006.

Each of these installations are monitored monthly by trained Amgen staff, using a handheld gas analyser, for the following parameters:

- Methane (CH₄)
- Carbon Dioxide (CO₂)
- Oxygen (O₂)
- Carbon Monoxide (CO)
- Hydrogen Sulphide (H₂S)
- Relative Pressure
- Atmospheric Pressure
- Installation Depth
- Depth to Water

The purpose of this monitoring is to detect whether any of the gas being produced by the landfill waste is migrating laterally towards off-site receptors.

4.2 Risk Assessment

Source

The source term with respect to landfill gas production at the Nant-y-Gwyddon Landfill Site is landfilled waste. Landfill gas is produced by the microbial breakdown of biodegradable waste. Landfill Gas contains a high proportion of methane (typically between 35% - 60% by Volume) and carbon dioxide (typically 16% - 57% by Volume); in addition to a number of trace components that may arise depending on the waste type deposited.

Pathway

If gas pressures within the landfill are high, then there is the potential for landfill gas to migrate towards the margins of the landfill where it could enter into the sub-surface. Depending on ground conditions, landfill gas has potential to migrate significant distances, towards on-site and off-site receptors.

The presence of an active gas extraction system at Nant-y-Gwyddon acts to minimise the risk of gas pressures building up within the landfill. This minimises the risk of sub-surface lateral emissions by creating a preferential pathway for any gas generated. In addition to this, the presence of the engineered containment system further reduces the likelihood of landfill gas escaping into the ground in significant quantities.

Receptor

The nearest residential properties to the landfill are located around 400 – 500 m south of the landfill site boundary in the village of Clydach Vale. The village of Gelli is located in excess of 500 m from the Northern boundary of the site. Both these villages are situated at a lower elevation to the site and are considered to be very low risk, when assessing potential sub-surface gas migration from the site.

4.3 Monitoring Results

Table 4.1 (page 26), provides a summary of the results of ARL's monthly LFG monitoring carried out at the site by ARL staff using the agreed methodology.

The results of sub-surface landfill gas monitoring carried out at Nant-y-Gwyddon throughout 2025 did not record the presence of elevated concentration of methane in any of the 115 samples taken. Elevated carbon dioxide and slightly reduced oxygen concentration have been recorded on occasions at each of the 10 functional ground monitoring installations used at the site. This is considered to represent background concentrations of these gases in the soil gas (sub surface gas samples) present at the site.

Annual average Methane (CH₄) concentrations calculated for the results of monitoring undertaken during 2025 are shown to be less than 0.3% CH₄ by Vol for each of the ground monitoring boreholes sampled. This indicates that there has been no detection of landfill gas migration at the site over the previous 12 months of monitoring.

Ground monitoring installation GMBH 5 recorded the highest concentration of carbon dioxide (5.6% CO₂ by Vol) in Jul-25. This was accompanied by a reduced Oxygen reading of 15.3%. The presence of carbon dioxide detected within this installation has not been attributed to landfill gas migration due to the absence of methane in the sample. Furthermore, there is no indication of elevated gas pressure within the monitoring installation. Monitoring of the relative pressure within the installation was low averaging less than 0.1 mbar over the 12 month period Jan-25 to Dec-25.

Considering the results of sub-surface landfill gas monitoring undertaken by Amgen staff at the Nant-y-Gwyddon Landfill Site throughout the period Jan-25 to Dec-25, there is no evidence to suggest that landfill gas is migrating into the ground strata surrounding the site.

Measures currently employed at the site to control landfill gas migration are shown to be protective of the environment and human health.

Table 4.1: Summary of sub-surface landfill gas monitoring undertaken by ARL at the Nant-y-Gwyddon Landfill during the period Jan 25 – Dec 25.

Parameter	NYG 1			NYG 4			NYG 6			NYG 7			NYG 8		
	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave
CH ₄ (%)	0	0.2	0.1	0	0.2	0.1	0	0.2	0.1	0	0.2	0.1	0	0.2	0.1
CO ₂ (%)	0.1	1.6	0.8	0.2	1.1	0.6	0.1	0.7	0.2	0.1	0.8	0.3	0.1	0.9	0.3
O ₂ (%)	18.8	21.3	20.4	19.9	21.2	20.7	20.2	21.8	20.9	20	21.4	20.9	17.9	21.5	20.4
CO (PPM)	0	1	0.3	0	1	0.4	0	1	0.2	0	1	0.4	0	1	0.3
H ₂ S (PPM)	0	0	0.0	0	0	0.0	0	0	0.0	0	0	0.0	0	0	0.0
Peak CH ₄ (%)	0	0.2	0.1	0.1	0.2	0.1	0	0.3	0.1	0	0.3	0.1	0	0.2	0.1
LEL (%)	0	4	2.2	0	4	2.2	0	4	1.3	0	4	1.8	0	4	1.8
Parameter	GMBH 5			GMBH 6			GMBH 7			GMBH 8			NYG 10		
	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave	Min	Max	Ave
CH ₄ (%)	0	0.2	0.1	0	0.2	0.1	0	0.2	0.1	0	0.2	0.1	0	0.2	0.3
CO ₂ (%)	0.5	5.6	2.7	0.1	1.7	0.5	0.2	1.7	0.9	0.1	1.1	0.4	0.1	1.7	0.4
O ₂ (%)	15.3	21.1	18.8	19.8	21.2	20.7	18.4	21.1	19.9	19.3	21.7	20.7	19.6	21.3	20.6
CO (PPM)	0	1	0.5	0	0	0.1	0	0	0.0	0	1	0.2	0	1	0.3
H ₂ S (PPM)	0	0	0.0	0	0	0.0	0	0	0.0	0	0	0.0	0	0	0.0
Peak CH ₄ (%)	0	0.2	0.1	0	0.3	0.1	0	0.3	0.1	0	0.3	0.1	0	0.2	0.1
LEL (%)	0	4	1.3	0	4	1.8	0	4	1.5	0	4	1.6	0	4	2.0

5. CONCLUSIONS

5.1 Overview

Amgen Rhondda Ltd. (ARL) have carried out environmental monitoring of leachate, groundwater, surface water and landfill gas at the Nant-y-Gwyddon landfill site throughout 2025, as specified in the site licence (Environmental Permit) and working plan.

The information collected during these exercises has been reviewed in sections 3 and 4 of this document and form part of the continual reporting of site activities to Natural Resources Wales (formerly EA Wales).

5.2 Landfill Leachate Levels and Contamination

Throughout 2025, ARL have taken monthly measurement of leachate levels within the landfill at Nant-y-Gwyddon. These have been taken from 2 locations situated within the waste, both of which extend to the base of the landfill.

Results show that leachate levels within the landfill at Nant-y-Gwyddon have been maintained below 1m throughout 2025 as required by the site's permit conditions.

ARL utilise 3 locations at the Nant-y-Gwyddon landfill site for the purpose of monitoring the concentrations of contaminants present within the landfill leachate (including 1 located directly in the waste cell). During this reporting period (Jan-25 to Dec-25), ARL carried out the required suite of laboratory analysis on 19 leachate samples collected from these locations.

Section 3.2 provides a comparison of ARL's analysis of contaminant concentrations in leachate sampled at Nant-y-Gwyddon with published average data for leachate in similar type UK landfill (see Table 3.3). It is shown that leachate currently being produced at the Nant-y-Gwyddon Landfill Site is relatively dilute when compared to national averages, as reported in DoE Research Report No. CWM 072/94 (DoE 1995). It has also been shown that there is no obvious trend in concentrations of leachate contamination present at the site. Each of the contaminants analysed remained fairly consistent in concentration (see Table 3.3 and Appendix D for reference).

5.3 Surface Water Quality

Throughout the period Jan-25 to Dec-25, ARL have carried out the required surface water monitoring at 6 locations on and around the Nant-y-Gwyddon landfill site. The results of a series of laboratory analysis carried out on 56 surface water samples collected at the site are presented, along with a comparison of associated EAL's.

Throughout 2025, surface water sampled on and around the Nant-y-Gwyddon Landfill Site has been shown to be of a good quality. There was no indication of leachate contamination in any samples taken in any of the 4 watercourses surrounding the site, with concentrations of ammoniacal nitrogen (NH_4 as N) very low in each of the 56 samples analysed.

When compared with the results of surface water monitoring undertaken in 2025, 2024 and 2023, it is evident that the high quality of water, observed during previous years has continued through 2025.

5.4 Groundwater Quality

The Nant-y-Gwyddon site is equipped with a total of 8 functional groundwater monitoring boreholes. The site has a number of other ground monitoring installations that do not yield groundwater and or have been adopted for landfill gas monitoring. During the period Jan-25 to Dec-25, ARL carried out the agreed suite of laboratory analysis on groundwater samples obtained from these monitoring installations.

The results of Groundwater monitoring undertaken by ARL at the Nant-y-Gwyddon Landfill Site during the period Jan-25 to Dec-25 have been reviewed as part of the ongoing stewardship of the Nant-y-Gwyddon Landfill Site. Results have been compared against site specific trigger and control levels in order to determine the environmental performance of the landfill.

Table 3.9 (section 3.4) provides a summary of results of groundwater monitoring, against the agreed control and trigger levels for the Nant-y-Gwyddon Landfill Site. It is noted that there was a single exceedance of a trigger point; a value of 0.65 mg/l NH₄ as N was returned for GW 6 in Nov-25. This was an isolated occurrence and is not thought to be indicative of ongoing leachate contamination at the site.

5.5 Sub-surface Landfill Gas Monitoring


Throughout 2025, ARL staff have undertaken monthly monitoring of landfill gas in 10 sub-surface boreholes located around the Nant-y-Gwyddon Landfill Site. Results show that there is no evidence to suggest that landfill gas is escaping from the base of the site. Current measures in place to control landfill gas migration are shown to be protective of the environment and human health.

6. RECOMMENDATIONS

Continue to obtain and review samples of water and soil gas on and around the Nant-y-Gwyddon Landfill Site in accordance with the approved Working Plan for the site.

APPENDIX A

Drawings



KEY



SITE BOUNDARY
LANDFILL AREA

SCALE 1:25,000		DATE _14/05/2024		DRAWN L.F.		PROJECT REVIEW OF ENVIRONMENTAL MONITORING RESULTS FOR NANT-Y-GWYDDON LANDFILL SITE _2023		DRAWING TITLE LOCATION PLAN (DRG NO. ARL2024/01/001)	
AMGEN RHONDDA NANT-Y-GWYDDON LANDFILL SITE NANT-Y-GWYDDON ROAD GELLI MID-GLAMORGAN CF41 7TL				REPRODUCED FROM ORDNANCE SURVEY 1:50,000 MAP OF 1991 WITH THE PERMISSION OF THE CONTROLLER OF HER MAJESTY'S STATIONERY OFFICE, CROWN COPYRIGHT, LICENCE NUMBER AL50604A.					



Phase 2 Area

Previously consisted of a 3 hectare area prepared for landfilling with the construction of a basal liner (completed in the early 1990's). No waste was ever deposited within this area.

Subsequently, the current site operator (Amgen) constructed 3 (14,000 m3 capacity) leachate holding lagoons (completed in Dec 2001) for the control of leacahte.

Both the basal liner and leachate lagoons have now been removed and the area restored with a shallow surface water lagoon.

Phase 1 Landfill Area

The Phase 1 landfill covers an area of approximately 9.5 hectares and was operated during the period November 1987 – March 2002. It contains approximately 1.25 million tonnes of Household, Commercial and Non-Hazardous Industrial Waste.

Now fully remediated and restored with the construction of an engineered landfill cap and surface water drainage infrastructure (completed September 2005).


NOTES:

KEY:

WML BOUNDARY

AREA OF LANDFILL WASTE

REV.	DESCRIPTION	DATE



AMGEN
Rhondda
ALTERNATIVE SOLUTIONS
IN WASTE MANAGEMENT

AMGEN RHONDDA LTD.
BRYN PICA
LLWYDGOED
ABERDARE
CF44 0BX

TEL: 01685 870770
FAX: 01685 874684

JOB TITLE


NANT-Y-GWYDDON
ENVIRONMENTAL REVIEW

DRAWING TITLE

GENERAL LAYOUT

DRAWN	DATE	STATUS
		FOR COMMENT ☐
		FOR APPROVAL ☐
		DRAFT ☐
		FINAL ☒

SCALE	SHEET	DRAWING NO.	REVISION
1: 2500	A2	AARL2026/ENV/01/002	—



LEACHATE CONTAMINATION MONITORING POINTS:


- LPS1 (LEACHATE PUMPING STATION JONES BUND)
- L5a (INSPECTION MANHOLE)
- L5 (LEACHATE HOLDING TANK)

NOTES:

KEY:

- WML BOUNDARY
- AREA OF LANDFILL WASTE
- LEACHATE DISCHARGE PIPEWORK (SURFACE)
- LEACHATE DISCHARGE PIPELINE (UNDERGROUND)
- LEACHATE INSPECTION CHAMBER /SUMP
- LEACHATE EXTRACTION POINT
- LEACHATE MONITORING PIEZOMETER

SCALE 1 : 250
PUMPING STATION DETAIL (JONES BUND)



REV.	DESCRIPTION	DATE



AMGEN RHONDDA LTD.
BRYN PICA
LLWYDCOED
ABERDARE
CF44 0BX


TEL: 01685 870770
FAX: 01685 874684

JOB TITLE
NANT-Y-GWYDDON
ENVIRONMENTAL REVIEW
2026

DRAWING TITLE
LEACHATE MANAGEMENT
AND MONITORING

DRAWN	DATE	STATUS
APPROVED	DATE	FOR COMMENT ☐
LF	14/05/26	FOR APPROVAL ☐
		DRAFT ☐
		FINAL ☒

SCALE	SHEET	DRAWING NO.	REVISION
1: 2500	A2	A20264/ENV/01/003	—



KEY

- VML BOUNDARY
- AREA OF LANDFILL WASTE
- SURFACE WATER MONITORING POINT

REV	DESCRIPTION	DATE



ANHEIM RESEARCH LTD
 100M FIDA
 LLYWYDDION
 ANHEIM
 CF44 0BX
 TEL: 01492 870070
 FAX: 01492 874624

FILE

NANT-Y-GWYDDION
 ENVIRONMENTAL REVIEW
 2026

PROJECT TITLE

SURFACE WATER
 MONITORING POINTS




			DATE FOR COMMENTS
APPROVED BY	LF	14/05/19	DATE FOR APPROVAL
			DATE FOR FINAL

DATE	PROJECT	PROJECT NO.	PROJECT NAME
14/05/19	A2	2026	ENV/DL/004



NOTES:

KEY:

-  WML BOUNDARY
-  AREA OF LANDFILL WASTE
-  GROUNDWATER MONITORING POINT

REV.	DESCRIPTION	DATE



AMGEN RHONDDA LTD.
BRYN PICA
LLWYDGOED
ABERDARE
CF44 0BX


TEL: 01685 870770
FAX: 01685 874684

JOB TITLE
**NANT-Y-GWYDDON
ENVIRONMENTAL REVIEW
2026**

DRAWING TITLE
GROUNDWATER MONITORING


			STATUS
			FOR COMMENT ☐
APPROVED		DATE	FOR APPROVAL ☐
LF		14/05/26	DRAFT ☐
			FINAL ☒

SCALE	SHEET	DRAWING NO.	REVISION
1: 2500	A2	ARI2026/ENV/01/005	—



SCALE 1 : 200

GENERAL LAYOUT OF LANDFILL GAS
POWER GENERATION COMPOUND




NOTES

KEY:

- WML BOUNDARY
- PHASE 1 LANDFILL AREA
- GAS MAIN
- GAS LINE (UNDERGROUND)
- GAS LINE (SURFACE)
- GAS EXTRACTION WELL WITH MONITORING POINT
- SUBSURFACE LANDFILL GAS MONITORING BOREHOLE
- LEACHATE INSPECTION CHAMBER
- LANDFILL GAS CONTROL MANIFOLD AND DEWATERING KNOCKOUT POT

REV.	DESCRIPTION	DATE



AMGEN RHONDDA LTD
BRYN PICA
LLWYDCOED
ABERDARE
CF44 0BX

JOB TITLE

NANT-Y-GWYDDON
ENVIRONMENTAL REVIEW
2026

DRAWING TITLE

LANDFILL GAS MANAGEMENT
AND MONITORING

APPROVED	DATE	STATUS
LF	14/05/26	FOR COMMENT ☐ FOR APPROVAL ☐ DRAFT ☐ FINAL ☒

SCALE	SHEET	DRAWING NO.	REVISION
1:1500	A1	ARL26/ENV/01/006	—

Monitoring Suites from Site Working Plan

Table 10: Leachate monitoring and sampling determinands:

Parameter	Monthly Suite	Quarterly Suite	Annual Suite	Lower Detection Limit mg/l	Action Threshold
1,2-Dichloroethane		✓	✓	0.002	
Acetone			✓	0.1	
Acrylonitrile			✓	0.1	
Alkalinity	✓	✓	✓	10	
Ammoniacal Nitrogen	✓	✓	✓	0.3	
Arsenic			✓	0.0005	
Benzene		✓	✓	0.002	
BOD	✓	✓	✓	1.3	
Cadmium		✓	✓	0.0002	
Calcium		✓	✓	0.01	
Chloride	✓	✓	✓	20	
Chromium		✓	✓	0.01	
COD	✓	✓	✓	17	
Conductivity	✓	✓	✓		
Copper		✓	✓	0.01	
Anionic Detergents and Surfactants			✓	0.2	
Dimethoxymethane			✓	0.1	
Dimethylethanolamine			✓	0.01	
Dissolved Oxygen				0.5	
Formaldehyde			✓	0.1	
Iron		✓	✓	0.01	
Lead		✓	✓		
Magnesium		✓	✓	0.0005	
Manganese			✓	0.001	
Mercury			✓	0.0005	
Methanol			✓		
Nickel		✓	✓	0.01	
Nitrate		✓	✓	0.4	
Nitrite		✓	✓	0.008	
pH	✓	✓	✓	n/a	
Phenol		✓	✓	0.11	
Phosphate		✓	✓	0.1	
Potassium		✓	✓	0.0005	
Propan-1-ol			✓	0.1	
Propan-2-ol			✓	0.1	
Propylamine			✓	0.01	
Sodium		✓	✓	0.0005	
Sulphate		✓	✓	0.1	
Sulphide		✓	✓	0.2	
Suspended Solids	✓	✓	✓	2	
Styrene		✓	✓	0.002	
Temperature	✓	✓	✓		
TOC	✓	✓	✓	2	
Toluene			✓	0.002	
Total Oxidised Nitrogen		✓	✓	0.4	
Trichloroethane		✓	✓	0.002	
Trichloroethylene		✓	✓	0.002	
Trimethylamine			✓	0.01	
Water/leachate level / piezometric head	✓	✓	✓	n/a	
Xylene		✓	✓	0.002	
Zinc		✓	✓	0.05	

Table 11a: Groundwater monitoring and sampling determinands:

Parameter	Monthly Suite	Quarterly Suite	Annual Suite
1,2-Dichloroethane		X	X
Acetone		X	X
Acrylonitrile		X	X
Alkalinity	X	X	X
Ammoniacal Nitrogen (ammonium as N)	X	X	X
Arsenic		X	X
Benzene		X	X
BOD	X	X	X
Cadmium		X	X
Calcium		X	X
Chloride	X	X	X
Chromium		X	X
COD	X	X	X
Conductivity	X	X	X
Copper		X	X
Anionic Detergents and Surfactants			X
Dimethoxymethane			X
Dimethylethanolamine			X
Dissolved Oxygen			
Formaldehyde			X
Iron		X	X
Lead		X	X
Magnesium		X	X
Manganese			X
Mercury			X
Methanol			X
Nickel		X	X
Nitrate	X	X	X
Nitrite	X	X	X
pH	X	X	X
Phenol		X	X
Phosphate		X	X
Potassium		X	X
Propan-1-ol			X
Propan-2-ol			X
Propylamine			X
Sodium		X	X
Sulphate		X	X
Sulphide		X	X
Suspended Solids	X	X	X
Styrene		X	X
Temperature	X	X	X
TOC	X	X	X
Toluene		X	X
Total Oxidised Nitrogen		X	X
Trichloroethane		X	X
Trichloroethylene		X	X
Trimethylamine			X
Water/leachate level / piezometric head	x	X	X
Xylene		X	X
Zinc		X	X


Table 12: Surface water monitoring and sampling determinands:

Parameter	Monthly Suite	Quarterly Suite	Annual Suite	Lower Detection Limit mg/l	Action Threshold
1,2-Dichloroethane		✓	✓	0.002	
Acetone			✓	0.1	
Acrylonitrile			✓	0.1	
Alkalinity	✓	✓	✓	10	
Ammoniacal Nitrogen	✓	✓	✓	0.3	
Arsenic			✓	0.0005	
Benzene			✓	0.002	
BOD	✓	✓	✓	1.3	
Cadmium		✓	✓	0.0002	
Calcium		✓	✓	0.01	
Chloride	✓	✓	✓	20	
Chromium		✓	✓	0.01	
COD	✓	✓	✓	17	
Conductivity	✓	✓	✓	100 µS	
Copper		✓	✓	0.01	
Anionic Detergents and Surfactants			✓	0.2	
Dimethoxymethane	-		✓	0.1	
Dimethylethanolamine	-		✓	0.01	
Dissolved Oxygen	✓	✓	✓	0.5	
Formaldehyde			✓	0.1	
Iron		✓	✓	0.01	
Lead		✓	✓		
Magnesium		✓	✓	0.0005	
Manganese			✓	0.001	
Mercury			✓	0.0005	
Methanol	-		✓		
Nickel		✓	✓	0.01	
Nitrate		✓	✓	0.4	
Nitrite		✓	✓	0.008	
pH	✓	✓	✓	n/a	
Phenol	-		✓	0.11	
Phosphate	-	✓	✓	0.1	
Potassium		✓	✓	0.0005	
Propan-1-ol	-		✓	0.1	
Propan-2-ol	-		✓	0.1	
Propylamine	-		✓	0.01	
Sodium		✓	✓	0.0005	
Sulphate		✓	✓	0.1	
Sulphide		✓	✓	0.2	
Suspended Solids	✓	✓	✓	2	
Styrene	-		✓	0.002	
Temperature	✓	✓	✓	0.1 C	
TOC	✓	✓	✓	2	
Toluene	-		✓	0.002	
Total Oxidised Nitrogen			✓	0.4	
Trichloroethane	-		✓	0.002	
Trichloroethylene	-		✓	0.002	
Trimethylamine	-		✓	0.01	
Water/leachate level / piezometric head				n/a	
Xylene	-		✓	0.002	
Zinc		✓	✓	0.05	


APPENDIX C

**Time Series Plots Illustrating the Results of ARL's Lab Analysis of
Leachate Sampled at the Nant-y-Gwyddon Landfill Site During the Period
Jan 10 – Dec 25.**


Lab analysis of pH levels in leachate sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2013 - Dec 2025.




Lab analysis of Electrical Conductivity levels in leachate sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2013 - Dec 2025.




Lab analysis of C.O.D. in leachate sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill
Site during the period Jan 2013 - Dec 2025.



Lab analysis of Ammonium (as N) in leachate sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2013 - Dec 2025.




Lab analysis of Chloride in leachate sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2013 - Dec 2025.




APPENDIX D

Time Series Plots Illustrating the Results of ARL's Lab Analysis of Surface Water Sampled at the Nant-y-Gwyddon Landfill Site During the Period Jan 10 – Dec 25.


**Lab analysis of pH values in surface water sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon
Landfill Site during the period Jan 2010 - Dec 2025.**




Lab analysis of Electronic Conductivity levels in surface water sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.




Lab analysis of Chemical Oxygen Demand (COD) concentrations in surface water sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.



Lab analysis of Ammoniacal Nitrogen levels in surface water sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.




Lab analysis of Chloride concentrations in surface water sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.




APPENDIX E

Time Series Plots Illustrating the Results of ARL's Lab Analysis of Groundwater Sampled at the Nant-y-Gwyddon Landfill Site During the Period Jan 10 – Dec 25.


Lab analysis of Electronic Conductivity levels in groundwater sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.




**Lab analysis of pH values in groundwater sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon
Landfill Site during the period Jan 2010 - Dec 2025.**



Lab analysis of Chemical Oxygen Demand (COD) concentrations in groundwater sampled at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025 (Scale 0-1500 mg/l).



Lab analysis of Ammoniacal Nitrogen levels in groundwater sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.



Lab analysis of Chloride concentrations in groundwater sampled by Amgen Rhondda Ltd at the Nant-Y-Gwyddon Landfill Site during the period Jan 2010 - Dec 2025.

