Docusign Envelope ID: DAC98716-269B-8820-8387-A3DB04030655

Permit Receipt Centre
Natural Resources Wales
Welsh Government Offices
Cathays Park
King Edward VII Avenue
Cardiff
CF10 3NQ
Tel: 0300 065 3000
Email: permitreceiptcentre@naturalresourceswales.gov.uk

APPLICATION FOR A MARINE LICENCE FOR MARINE WORKS

Marine Works include, but are not limited to, coast defences, beneficial uses of dredged materials, subsea cables, pontoons, jetties, land reclamation, grab samples and outfall pipes under the Marine and Coastal Access Act 2009

Please read the notes carefully before completing the form.

- The Marine Licensing Team (MLT) administers Part 4 of the Marine and Coastal Access Act 2009 on behalf of the Licensing Authority, the Welsh Ministers.

- The completed application form must be accompanied by a location plan and, where appropriate, descriptive drawing(s) and any supporting environmental assessments.

- Please submit applications to the **Permit Receipt Centre** via the details at the top of this form. For applications larger than 20MB, we would advise that you contact us to determine the most appropriate method for submitting your application.

- Please submit marine licence applications, including this form and all supporting documents, **at least 4 months before the licence is required.**

  Some projects may raise matters that require a significantly longer time for consideration. These are most likely to be:

  - Projects that fall **within** The Marine Works (Environmental Impact Assessment) Regulations 2007 – as amended requiring an Environmental Statement
  - Large scale projects with substantial volumes of material being deposited or excavated
  - Works requiring an Appropriate Assessment to be conducted under The Conservation of Habitats and Species Regulations 2017.

- Information should be provided about the anticipated **duration of the entire project** in respect of works below/seaward of Mean High Water Spring (MHWS). Where appropriate, planned phasing of the work for which consent is sought must be detailed. For projects lasting more than one calendar year, planned phasing details must be given for each 12 month period.

A licence fee is payable in respect of an application. Details of fees can be found on our web pages.

Please note applications will not be processed without the correct relevant fee or invoicing details.

- Payments can be made via Cheque, BACS or credit/debit card.
  - Cheques should be crossed and made payable to **Natural Resources Wales**.
  - For BACS payments ensure you provide the reference number (not remittance number)

  Further information on payment methods can be found on our web pages.

- **All activities need to comply with the Water Framework Directive (WFD). The framework and guidance can be found on the Natural Resources Wales website,**

http://naturalresources.wales. The results of your WFD assessment must be attached to your marine licence application.

- Please answer all questions. If any information is not available at the time of application please indicate in the relevant section, giving reasoning in a covering letter. Outstanding details must be submitted as soon as possible. Any delay in forwarding details is likely to result in delays in determining your application.

  Your application may not be considered complete and therefore not processed until key information has been submitted. Your application may be returned if you fail to submit outstanding information within given timescales.

- Please note any licence may have conditions that must be discharged before works can commence. This will take additional time.
- If you have any queries with regards to completing this application please contact the MLT: marinelicensing@naturalresourceswales.gov.uk

How your application will be processed by the MLT:

- Submit all application to the **Permit Receipt Centre** via the details at the top of this form.

- Checked and acknowledged by the MLT within 21 days of receipt of application and payment

- If the application is complete and no further information is needed at this time, your application will be placed in a work queue to be assigned a permitting officer

- If the application is not complete, further information will be request and need to be provided before the application can be considered as complete

- Our **4 months** service level for determining non-EIA applications will begin from the date the **completed** application is received (*Please note some projects may take significantly longer than 4 months to determine due to their nature)*

- EIA projects may take significantly longer due to their scale and complexity. Therefore we encourage early engagement with the MLT

- Your application and supporting documents will be sent to for an initial consultation period of 28 days *(42 days for EIA projects)*

- For the majority of projects, a public notice must be advertised. Public consultation will be 28 days (*49 days for EIA projects*). For EIA projects a second public notice will be required. The MLT will advise on how this should be done.

- Responses to consultation will be considered and additional information requested at this time, if necessary.

- A decision on your Marine Licence Application will be made

All information submitted may be referred to within a licence, therefore all works must be in accordance with this information, unless otherwise agreed with NRW acting on behalf of the Licensing Authority during the determination process.
It is the responsibility of the applicant to obtain any other consents/authorisations that may be required.

Docusign Envelope ID: DAC98716-269B-8820-8387-A3DB04030655

Application Form Structure

1. Project Description and Cost
2. Applicant Details
3. Details of Agent, Contractor, Vehicles and/or Vessels used to carry out works
4. Environmental Impact Assessment (EIA)
5. Licensable Period
6. Project Description
7. Methods Statement
8. Materials of Project
9. Beach Replenishment, Land Reclamation or Salt Marsh Feeding
10. Temporary Works
11. Dredge and Disposal of Dredge Material
12. Protected Sites
13. Other Consents
14. Statutory Powers
15. Public Register
16. Application Fee
17. Declaration

Check List

Please ensure that you have included all the necessary information before you submit your application. **If any of the below are not completed in the application form, the application is likely to be considered incomplete and may be returned to you**

Item	Yes (√)
The applicant is a legal entity?	√
The declaration is signed by the applicant?	√
Is the application fee correct?	√
Are the grid references/coordinates correct?	√
Do the coordinates match map locations?	√
Have all the relevant supporting documents been submitted?	√
Has a clear methodology been provided in the application form?	√
Has Protected sites information been included?	√
Has a Water Framework Directive (WFD) assessment been submitted?	√
Are all the continuation sheets for application questions appended with correct corresponding numbers?	√

Should you have any queries regarding you application please contact the MLT via marinelicensing@naturalresourceswales.gov.uk

1. Project Description and Cost

1 (a). Project Name

Mona Offshore Windfarm Transmission Export Cable Shallow Geotechnical Survey

1(b). Please provide a brief description of the proposed project, including location

The proposed shallow geotechnical survey is located within the Mona Offshore Wind Project Transmission Export Cable Corridor (ECC) and Mona Array Area. The geotechnical survey is aiming to commence in December 2026. The objective of this geotechnical survey is to establish the characteristics and properties of the different seabed substrates along the ECC to inform the design of the Mona export cable. Data will be acquired to investigate the seabed conditions relevant to export cable design, routing and evaluation of installation and protection methods.

The surveys proposed within this Marine Licence Application (MLA) consist of:

- Shallow geotechnical surveys, including:
  - Up to 250 vibrocores;
  - Up to 10 boreholes (in the event of sample refusal from vibrocore sampling);
  - Up to 620 Cone Penetrometer Testing (CPT) samples, and
  - Up to 620 Thermal Resistivity Testing (TRT) samples.

It is noted that as CPTs and TRTs do not involve the removal of any seabed sediment, these are considered non-licensable activities under the Marine and Coastal Access Act. These activities have been included in this SID for completeness and for information only.

1(c). Please provide an estimated gross cost of the project (Inc. materials and labour) for works that fall below/seaward of Mean High Water Springs (MHWS)

>£1,000,000

2. Applicant Details

To whom the licence will be issued. *This must be a legal entity such as an individual, registered company/ charity or public body.*

Title	Mr	Full Name	Richard Haydock
Company or Trading Name	Mona Offshore Wind Limited		
Company Registration Number (if applicable)	13497266		
Name of Contact or individual (if different)			
Position in Company	Mona Project Director		

Address inc. postcode (provide registered Company address if applicable)	MYO One New Change London EC4M 9AF
Telephone Number	+44 07792012870
Email Address	mona.consents@jnbp.com

3. Details of Agent, Contractor, Vehicles and/or Vessels used to carry out works

3(a). Agent Details

This is who we will correspond with unless otherwise informed. If no agent we will contact the applicant.

Title	Mr	Full Name	Ben Peacock-Jones

Company or Trading Name	GoBe Consultants Ltd
Company Registration Number (if applicable)	06845190
Name of Contact or individual (if different)	
Position in Company	Senior Consultant
Address (Inc. postcode)	Suites B2 & C2, Higher Mill Lane, Buckfastleigh, Devon TQ11 0EN
Telephone Number	+44 (0)1626 323890
Email Address	benjones@gobeconsultants.com

3(b). Does the Applicant wish to be included in all correspondence? Yes ☒ No ☐

3(c). Contractor Details
In order for contractors to benefit from the licence permission, details must be provided.
Any details not provided with application must be confirmed before operations commence.

Contractor Company or Trading Name	Address
TBC	

3(d). Will the works require the use of vessels? Yes ☒ No ☐

3(d) (i).Vessel Details (if applicable and available)
In order for contractors to benefit from the licence permission, details must be provided.
Any details not provided with application must be confirmed before operations commence.

Operator	Name of Vessel	Type of Vessel	Vessel Registration Number	Country of Registration
TBC				

3(e). Will the works require the use of vehicle? Yes ☐ No ☒

3(e) (i). Vehicle Details (if applicable and available) to be used below MHWS
In order for contractors to benefit from the licence permission, details must be provided.
Any details not provided with application must be confirmed before operations commence.

Operator	Type/Description of Vehicle
N/A	

3(f). If the contractor or vessels or vehicles are not known at the application stage, when do you expect to provide these details?
These details will need to be confirmed prior to the licence and operations commencement

Contractor and vessel details will be confirmed and provided prior to the works commencing.

4. Environmental Impact Assessment (EIA)

Certain projects, due to their scale, location and/or nature, may require an EIA under the Environmental Impact Assessment Directive (Directive 85/337/EEC – as amended). If a project qualifies under EIA, an Environmental Statement (ES) must be prepared and submitted with the application.

Projects that fall within Annex I of the Directive automatically require an EIA. Projects that fall within Annex II of the Directive are assessed on a case-by-case basis for the requirement for an EIA to be undertaken.

4(a). Do you consider the works to be under the Environmental Impact Assessment Directive (Directive 85/337/EEC – as amended)? Yes ☐ No ☒

4(a) (i) If Yes, which Annex does the proposal fall under? Annex I☐ Annex II☐

4(a) (ii) Which number(s) within the Annex does the proposal relate to?

4(b). Have you applied for a screening or scoping opinion from the MLT under the Marine Works (Environmental Impact Assessment) Regulations 2007 (as amended)? Yes ☐ No ☒

4(b) (i). If Yes, please provide the reference number | |

4(c). Has an Environmental Impact Assessment been undertaken? Yes ☐ No ☒

4(c)(i). If Yes, has an Environmental Statement been submitted to support this Marine Licence application? Yes ☐ No ☐

4(d). If an Environmental Impact Assessment has been undertaken, but an ES has not been submitted, please provide an explanation

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

5. Licensable Period

Determination of applications will be based on the works taking place during these dates. Please ensure you have included an adequate contingency period. If works are not completed by the Requested Licence Expiry Date you may be required to submit a new application. *Including a contingency period within your original application does not impact on Licence Fee*

Start Date	01 December 2026	**Requested Licence Expiry Date**	31 October 2028

Please ensure you submit your application for a Marine Licence ***at least 4 months*** *prior to the intended start date. Some projects, such as EIA projects, will take significantly longer to determine.*

6. Project Description

6(a). Please give a description of the proposed project.

This should include the purpose of the project, estimated timescales of construction and operation, and broken down by the phases of works, if applicable.
Details should include, but not be limited to, dimensions of project, quantity of material being deposited and removed.

The objective of this geotechnical survey is to establish the characteristics and properties of the different seabed substrates along the ECC to inform the design of the Mona export cable. Data will be acquired to investigate the seabed conditions relevant to export cable design, routing and evaluation of installation and protection methods.

Shallow geotechnical samples within the Mona Transmission ECC will be undertaken with a combination vibrocore sampling, CPTs and TRTs. Up to 250 vibrocore samples will be taken with a maximum total volume of 16.35 m^3. A maximum of 10 locations may be investigated using borehole sampling, in the event of sample refusal when using a vibrocore or equivalent sampling methodology. In the event that 10 locations are investigated using boreholes, a maximum estimated volume of material to be removed is approximately 0.654 m^3. It is worth noting that this volume of 0.654 m3 sits within the maximum volume established above, with the total sample volume for all methodologies being 16.35 m^3. Details surrounding the seabed frame for sample collection is currently unknown, although the maximum potential footprint of the seabed frame is 3.5 m x 3.5 m (12.25 m^2) per sample. Therefore, for the 250 vibrocores (including potential 10 boreholes) the maximum footprint is 3,062.5 m^2, for the 620 CPTs and TRTs (noting they will be undertaken in parallel so the footprint is shared) the maximum footprint is 7,595 m^2.

The geotechnical surveys are planned to be undertaken from December 2026. A ML is requested for the period from 1 December 2026 to 31 October 2028 to provide sufficient flexibility for weather, vessel availability and potential changes to the survey programme.

Please see the accompanying Supporting Information Document for further information.

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

6(b). Please detail the location of the proposed construction project.
These should be Latitude and Longitude coordinates (WGS84) in decimal degrees to 5 decimal places (e.g. Lat 52.12345 Long -4.12345), defining the extent of the project.

The geotechnical survey will be undertaken within the Mona Transmission ECC and Array Area within Welsh waters. A supplementary excel file is included with the application detailing the site boundary. The exact sample locations have not yet been determined and will be informed by geophysical survey data, but will be located within the Mona Transmission ECC and Array Area.

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

6(c). The following must be provided with the completed application form:

(i) a suitably scaled extract of an Ordnance Survey Map or Admiralty Chart with location of project, complete with **North Arrow** and **Scale**

(ii) construction plans and sectional drawings showing those proposed works below/seaward of MHWS, which should give details of the materials to be used (for beach replenishment the quantity, particle size and source of material to be deposited and deposit location is also required).

(iii) a descriptive schematic drawing and suitably scaled location plan which show the full extent of the project clearly in relation to the surrounding area and features.

Please list below **all supporting documents** that have been submitted with this application, including suitable documents/maps/drawing titles and reference numbers

Mona_ECC_Geotechnical_Survey_Marine_Works_Licence_Application_Form Mona_ECC_Geotechnical_Survey_Marine_Works_Licence_Application_Form_Additional_Sheets Mona_ECC_Geotechnical_Survey_Marine_Licence_Supporting_Environmental_Information Mona_ECC_Geotechnical_Survey_Marine_Licence_Coordinates Mona_ECC_Geotechnical_Survey_Marine_Licence_Area Mona Project DCO Order Limits shapefile (.shp.zip) and PDF chart

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

The applicant should note that these drawings/plans may be copied to others as part of the MLT's consultation procedures. If they are subject to copyright, it is the **responsibility of the applicant to obtain the necessary approvals to reproduce the documents.**

7. Methods Statement

7(a). Please provide a detailed method statement for the works
This must include methods for all works including temporary structures or deposits such as jetties, cofferdams, moorings or landing stages to be constructed seaward of MHWS

Please see attached Supporting Information Document for full details.

Up to 250 shallow geotechnical samples within the Mona Transmission ECC will be undertaken. The geotechnical sampling work will consist of vibrocore sampling up to 102 mm in diameter to a maximum depth of 8 m. The volume of each core will be up to 0.0654 m^3, with a total collected volume of 16.35 m^3. Geotechnical samples will be taken for laboratory analysis and testing. A maximum of 10 locations may be investigated using borehole sampling, in the event of sample refusal when using a vibrocore or equivalent sampling methodology. In the event that 10 locations are investigated using boreholes, a maximum estimated volume of material to be removed is approximately 0.654 m^3. It is worth noting that this volume of 0.654 m^3 sits within the maximum volume established above, with the total sample volume for all methodologies being 16.35 m^3. Geotechnical samples via coring will be taken for laboratory analysis and testing. With a maximum footprint of 12.25 m^2 per sample, for the 250 vibrocores (including potential 10 boreholes) the maximum footprint is 3,062.5 m^2, and for the 620 CPTs and TRTs (noting they will be undertaken in parallel so the footprint is shared) the maximum footprint is 7,595 m^2. In situ testing will also be undertaken with a CPT tool. A minimum of three types of cone will be mobilized of cross-sectional areas of 5 cm^2, 10 cm^2, and 15 cm^2, respectively. TRT will also be undertaken as part of in situ testing at selected CPT and vibrocore locations. It is noted that as CPTs and TRTs do not involve the removal of any seabed sediment, these are considered non-licensable activities under the Marine and Coastal Access Act. These activities have been included in this SID for completeness and for information only.

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

7(b). Do you intend to undertake activities that could generate underwater noise?
This include piling, use of explosives, geophysical, acoustic deterrent devices and multibeam echosounders. Yes ☐ No ☒

7(b) (i). If Yes, what type(s) of activities will be undertaken?

7(b) (ii). If Yes, approximately how many days will the activity be undertaken for?

If Yes, you will be required to complete an additional form that will be provided.

7(c). Please state the measures to be taken to:

(i) Minimise risk to the marine environment

Please see attached Supporting Information Document and Biosecurity Risk Assessment (Appendix C).

(ii) Prevent undue interference to others

Notifications to Mariners will be issued to ensure mariners are made fully aware of the activity, including notices to fishing organisations, local port authorities and other relevant stakeholders.

Please see attached Supporting Information Document accompanying this application form for further information.

(iii) Maintain navigational safety, including marking and lighting of works

Notifications to Mariners will be issued to ensure mariners are made fully aware of the activity, including notices to fishing organisations, local port authorities and other relevant stakeholders.

The survey will comply with all maritime safety related legislation and guidance, including the Convention on the International Regulations for Preventing Collisions at Sea (COLREGs).

Please see attached Supporting Information Document accompanying this application form for further information.

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

8. Materials of Project

8(a). Description of materials to be deposited seaward of MHWS (Please tick all that apply)

Timber	☐	Iron/Steel	☐	Concrete	☐	Biocides/other chemicals	☐
Silt	☐	Stone/Rock	☐	Gravel	☐	Plastic/Synthetics	☐
Sand	☐	Other	☐				

If other, please provide a description of materials.

N/A

8(b). Delivery method of materials to site

If sea delivery, please include details of vessels to be used with a chart of proposed route and transhipment area. If vehicle delivery, please provide the proposed access route.

N/A

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

8(c). Will the works involve removals seaward of MHWS? Yes ☒ No ☐

8(c) (i). Description of materials to be removed seaward of MHWS (Please tick all that apply)

Timber	☐	Iron/Steel	☐	Concrete	☐	Biocides/other chemicals	☐
Silt	☒	Stone/Rock	☒	Gravel	☒	Plastic/Synthetics	☐
Sand	☒	Other	☒				

8(c) (ii). Description of objects/materials to be removed seaward of MHWS
Including quantities to be removed.

250 samples (vibrocore sampling/equivalent methods, including up to 10 borehole samples):
- Diameter: 102 mm
- Maximum depth: 8 m
- Total volume collected per sample: 0.0654 m^3
- Total volume collected: 16.35 m^3

9. Beach Replenishment, Land Reclamation or Salt Marsh Feeding

For works involving any of the above, please provide the following information

9(a). Is the material to be deposited like for like to existing material? Yes ☐ No ☐

9(a)(i) If No for Beach Replenishment please provide justification why?

Not Applicable.

9(b). Description of material to be deposited
Please provide the grading specification of materials to be used, if using a range of grain sizes please state the percentage by weight passing. *If unsure, please refer to the Wentworth Scale*

N/A

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

9(c). Source of the material to be deposited
Including dredged or land based stating the origin of material

N/A

9(d). Has the material been chemically analysed? Yes ☐ No ☒
If material has been analysed, we may request this information to determine the application

9(d) (i) If Yes, is the analysis data been included with the application? Yes ☐ No ☐ N/A

10. Temporary Works

10(a). Will there be any temporary deposits below MHWS? Yes ☐ No ☒
This includes construction materials, removed objects/material, jetties or cofferdams
If **Yes**, please continue with section **10**

10(b). Please provide the location of temporary deposits
Please include a map/chart displaying the location of temporary deposits, if necessary.

No temporary deposits made.

10(c). Description of temporary deposits

No temporary deposits made.

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

11. Dredge and Disposal of Dredge Material

If you are undertaking Dredge and Disposal activities please also complete the Dredge and Disposal application form and submit together.

11(a). Do you intend to apply for a marine licence to dispose of dredged material to sea as part of the works in this application? Yes ☐ No ☒

12. Protected Sites

Licensing Authorities have a duty to ensure that projects will **not have significant adverse environmental impact**, particularly on any designated **European Site of Conservation Importance - Special Areas of Conservation (SAC) and Special Protection Areas (SPA), listed under the Habitats Directive (Council Directive 92/42/EEC on the conservation of natural habitats and of wild fauna and flora).** In addition, it is Government Policy that Wetlands of International Importance (Ramsar sites) are also considered as European Sites. There is a duty to take reasonable steps to further the conservation and enhancement of nationally designated sites (Sites of Special Scientific Interest (SSSIs).

12(a). Have you had pre-application correspondence with NRW, its legacy bodies or Natural England? Yes ☐ No ☒

12(a)(i). If Yes, please provide copies of correspondence with application and state which team(s) you have contacted?

12(b). Are any part of the works located *within* or *likely to affect* a designated conservation site? (SAC, SPA, SSSI or Ramsar) Yes ☒ No ☐

12(b)(i). If Yes, which designated site(s) may be affected?

- Liverpool Bay/ Bae Lerpwl SPA
- Y Fenai a Bae Conwy/ Menai Strait and Conwy Bay SAC
- Dee Estuary/Aber Dyfrdwy SAC
- River Dee and Bala Lake/Afon Dyfrdwy a Llyn Tegid SAC
- Ardal Cadwraeth Arbennig Bae Ceredigion/ Cardigan Bay SAC
- North Anglesey Marine/ Gogledd Môn Forol SAC
- Pen Llŷn a'r Sarnau/ Lleyn Peninsula and the Sarnau
- West Wales Marine SAC

Detail has been provided on an additional sheet.

12(c). Please provide a description of all mitigation measures proposed to avoid any impact on designated conservation sites.

Best practice vessel management measures to minimise disturbance to ornithology will be adhered to (these measures are further described in the DCO Application for the Mona Offshore Wind Project, 2024: Measures to minimise disturbance to marine mammals and rafting birds from transiting vessels. Deadline 5. [J17 F03]), including:

- Adhering to the Wildlife Safe (WiSe) Scheme;
- Use of regular vessel transit routes which follow, where possible, established shipping routes to minimise disturbance to ornithology;
- Where it is necessary for vessels to go outside of established navigational routes during transit to/from port and working areas, routes will be pre-selected to avoid locations where birds are known to aggregate and visible aggregations of rafting birds (inside or outside of the Liverpool Bay/Bae Lerpwl SPA) will be actively avoided within the limitations of vessel safety and manoeuvrability.

Additionally, no works will be completed within the Liverpool Bay SPA plus a 2 km buffer between 01 November and 31 March.

Please continue on a separate sheet if necessary. Please tick if you have done this ☒

12(d). If the works are not located *within* or *likely to affect* a designated conservation site, please indicated the approximate distance to the nearest designated conservation site.

Please note that if the proposed works are in or within 2km of a European Site of Conservation Importance you will have to provide suitable mitigation measure to avoid any impact on designated conservation sites.

13. Other Consents

Please detail all consents that you have applied for or received for these works

Type of Consent	Applied for	To be applied for	Reference Number	Date of Issue and Expiry
Planning Permission under Town and County Planning Act 1990 – From Local Planning Authority (LPA)				
Name and Address of LPA for location of works				
Land Owners Consent such as The Crown Estate Consent		x		
Port Authority or Local Harbour permissions				
Other NRW consents *such as Flood Defence or SSSI assent*				
Details of NRW consent				
Other consents *such as Transport and Works Act Order, Section 36 Electricity Act, grant/loan sanction*				
Details of other consents				

Docusign Envelope ID: DAC98716-269B-8820-8387-A3DB04030655

14. Statutory Powers

14(a).Does the applicant have statutory powers to consent any aspect of the project?
E.g. coast protection authority, dredging powers, statutory undertakers Yes ☐ No ☒

14(a)(i).If Yes, please give details and state the relevant legislation that gives these powers

Under The Marine Licensing (Register of Licensing Information)(Wales) Regulations 2011 and the Environmental Impact Assessment Directive (Directive 85/337/EEC – as amended), all information contained within or provided in support of this application will be placed on the Public Register unless NRW approve of the applicant's reasons for withholding all or part.

15. Is there any information contained within or provided in support of this application that you consider should NOT be included on the Public Register on the grounds that its disclosure:

15(a). Would be contrary to the interest of National Security? Yes ☐ No ☒

15(b). Would prejudice to an unreasonable degree you, or some other person's commercial interest of those of a third party? Yes ☐ No ☒

If **Yes** to either (a) or (b), please provide full justification as to why all or part of the information you have provided should be withheld

Please continue on a separate sheet if necessary. Please tick if you have done this ☐

16. Application Fee

16(a). What are the corresponding fee band for this application? Band 2 ☐ Band 3 ☒

16(b) Band 2 Only
Projects are charged at a fixed fee of £1920. The application will not be processed until the correct fee has been provided.

Please provide the method of payment

Method	Yes (√)	Reference Number
Cheque		
BACS (not remittance no.)		
World Pay (phone)		

16(c) Band 3 Application only
Band 3 applications are charged at on hourly rate of £120 and are invoiced in arrears. Please complete the details below which will be required for invoicing.

Customer Name	Ben Peacock-Jones
FAO	
Purchase order number	4500005948
Address for invoice	Suites B2 & C2, Higher Mill Lane, Buckfastleigh, Devon TQ11 0EN
Telephone Number	+44 (0)1626 323890
Email Address	benjones@gobeconsultants.com

Docusign Envelope ID: DAC98716-269B-8820-8387-A3DB04030655

17. Declaration

I declare that to the best of my knowledge and belief that the information given in this application form and supporting documentation is true.

WARNING: It is an offence under the Marine and Coastal Access Act 2009, under which this application is made, to fail to disclose information or to provide false or misleading information and can invalidate any licence granted.

Signature Signed by: Richard Haydock ECDE62E45D1D47B... **Date** 11 September 2026 | 16:20

Name *(in capitals)* RICHARD HAYDOCK

Position in Company MONA PROJECT DIRECTOR

*Applications cannot be processed unless signed by the **Applicant** (not agent), the applicant must have appropriate level of authority within the company.*

Applications will not be processed unless signed