



KEY

- SITE BOUNDARY
- 4m WIDE CONSTRUCTION ACCESS ROUTES: WET HEATHLAND TURFS LIFTED FOR TRANSPLANTING TO LAKE MARGINS. ROUTES PROTECTED WITH PROPRIETARY BOG MAT SYSTEM.

IMPORTANT
HEALTH, SAFETY & ENVIRONMENTAL INFORMATION

THE DESIGN PRESENTED ON THIS DRAWING HAS BEEN DEVELOPED IN ACCORDANCE WITH THE CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2015. ANY CONSTRUCTION LIMITATIONS ARISING FROM THE DESIGN AND SIGNIFICANT RESIDUAL RISKS NOT USUALLY ASSOCIATED WITH THE PROPOSED TYPE OF WORK ARE IDENTIFIED ON THE DRAWING OR WITHIN THE NOTES.

IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT.

TENDER ISSUE

- NOTES**
- ALL LEVELS IN METRES AT ORDNANCE DATUM UNLESS NOTED OTHERWISE.
 - ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.
 - NO DIMENSIONS ARE TO BE OBTAINED BY SCALING DRAWINGS.
 - REFER TO DRAWING P1845-002 FOR NOTES RELATING TO THE DRAWINGS
 - GUIDANCE AVAILABLE IN SALIX DOCUMENT "COIR PALLETS INSTALLATION GUIDE VERSION 1.2"
 - GUIDANCE AVAILABLE IN SALIX DOCUMENT "COIR ROLLS INSTALLATION GUIDE VERSION 2.0"
 - ROLLED EROSION CONTROL MATTING TO BE INSTALLED IN ACCORDANCE WITH SALIX DOCUMENT "RECP INSTALLATION GUIDE VERSION 1.0"
 - A TOTAL OF 800m² OF PREPLANTED COIR PALLETS SHALL BE FREE ISSUED TO THE CONTRACTOR BY THE EMPLOYER TO BE INCORPORATED AS SHOWN WITHIN THE WORKS
 - CONTRACTOR TO CARRY OUT THEIR OWN ON SITE ASSESSMENT OF DIMENSIONS WHERE POSSIBLE

rev	description	by	date	chk'd	auth
C	FOR TENDER - SETTLING PONDS REMOVED	MT	24/11/21	JH	DSL
B	FOR TENDER	MT	18/10/21	JH	DSL
A	DRAFT FOR CLIENT REVIEW	MT	29/09/21	JH	DSL

Stillwater Associates
Reservoir Safety & Water Consultancy

Alma House - Suite 3, Alma Road, Reigate, Surrey, RH2 0AX
T: +44 (0)1737 768237
E: office@stillwater-associates.co.uk
www.stillwater-associates.co.uk

© copyright reserved

client **Dŵr Cymru Welsh Water**

project **Llyn Bran Reservoir Discontinuance**

size	original scale	designed/drawn	checked	authorised
A1	1:2000	JH/MT	JH	DSL
status	drawing number	date	date	date
T	P1845-201	29/09/21	29/09/21	29/09/21