

- NOTES:
- DIMENSIONS**
    - ALL DIMENSIONS IN MILLIMETRES AND ALL LEVELS IN METRES TO ORDNANCE DATUM (NEWLYN) UNLESS STATED OTHERWISE.
    - DO NOT SCALE FROM THIS DRAWING. ONLY FIGURED DIMENSIONS AND LEVELS ARE TO BE USED.
    - GROUND LEVELS ARE FROM TOPOGRAPHICAL SURVEY CARRIED OUT IN 2020. THEY SHOULD BE VERIFIED PRIOR TO CONSTRUCTION
  - GEOTECHNICS**

NO GROUND INVESTIGATION HAS BEEN CARRIED OUT. IT IS ASSUMED THAT THE RIVER BED IS FORMED OF GRANULAR MATERIAL ON THE BASIS OF VISUAL INSPECTION. BEDROCK IS VISIBLE IN THE CHANNEL IN THE PROXIMITY OF THE WORKS, AND IT IS POSSIBLE THAT ROCKHEAD MAY BE ENCOUNTERED DURING THE REGRADING WORKS. THE CONTRACTOR IS TO CONFIRM THIS PRIOR TO COMMENCING WORKS AND INFORM THE PROJECT MANAGER IF THIS IS NOT THE CASE.
  - ENVIRONMENTAL SURVEYS.**

BAT AND OTTER SURVEYS ARE TO BE CARRIED OUT IN SPRING / SUMMER 2021 TO CONFIRM THE PRESENCE OF BATS AND OTTERS AT THE SITE. MITIGATION MEASURES ARE TO BE CONFIRMED PRIOR TO STARTING WORKS.
  - FOOTPATH REINSTATEMENT**

FOOTPATH TO BE REINSTATED ON ROUTE SHOWN IN LINE WITH CRUSHED STONE SURFACE DETAIL ON DRAWING TD-L-004
  - LANDSCAPING**

AREA INDICATED ON DRAWING IS A DISUSED QUARRY TO BE USED FOR THE PLACEMENT OF MATERIAL TAKEN FROM THE WEST RIVER BANK FOLLOWING REGRADING. SUBJECT TO ECOLOGICAL SURVEYS.
  - REFER TO DRAWINGS**

277161-ARP-04-XX-DR-XX-0004  
277161-ARP-04-XX-DR-XX-0008  
277161-ARP-04-XX-DR-XX-0011

THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS, SPECIFICATIONS AND CONTRACT DOCUMENTS. NOTIFY THE PROJECT MANAGER OF ANY DISCREPANCIES BEFORE PROGRESSING.

- LEGEND:
- EXISTING PUBLIC RIGHT OF WAY
  - EXISTING FOOTPATH
  - PROPOSED FOOTPATH ROUTE

**SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION**

IN ADDITION TO THE HAZARDS/RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING:



**CONSTRUCTION**

- STABILITY OF EXISTING STRUCTURES - RISK OF COLLAPSE
- POSSIBLE PRESENCE OF BATS IN RECORDER HOUSE
- POTENTIAL FOR WHITE-CLAWED CRAYFISH IN RIVER - PRECAUTIONARY WORKING METHODS REQUIRED
- COLLAPSE OF TREES DUE TO LOSS OF SUPPORT
- WORKING IN WATER - RISK OF DROWNING / FLOOD EVENTS

**DECOMMISSIONING / DEMOLITION**

- STABILITY OF EXISTING WEIR - POSSIBILITY OF COLLAPSE

REFER TO THE DESIGNERS RISK REGISTER FOR FURTHER DETAILS. IT IS ASSUMED THAT ALL THE WORKS ON THIS DRAWING WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WHO HAS CARRIED OUT A COMPREHENSIVE RISK ASSESSMENT.

C01	FOR CONSTRUCTION		JS	PS	RC	07/05/21
Rev.	Description		Drawn	Chkd	Appd.	Issue Date
<div><div></div><div><b>Cyfoeth Naturiol Cymru</b> <b>Natural Resources Wales</b></div></div>			<div></div>			
Project Name: SALMON FOR TOMORROW PHASE 2 HONDDU FORGE						
Drawing Title: PROPOSED WEIR PLAN						
Suitability: FOR CONSTRUCTION					Suitability Code: A	
Internal Project Number: 277161			Scale: 1:200		Rev. C01	
Drawing Number: 277161 - ARP - 03 - XX - DR - XX - 0006						