

37054



OUTGOING



PERMIT

~~Appointed~~Current Licence - Aug '07 - ~~deput~~, replaced Aug '07

No. L/1/29

CONTROL OF POLLUTION ACT 1974
PART I

WASTE DISPOSAL LICENCE

THE * GLYNDWR DISTRICT COUNCIL

HEREBY GRANT a Waste Disposal Licence, pursuant to an application dated
24 NOVEMBER 1992, in respect of the following:

Full name and address of licence holder	BFI WASTECARE LTD (mod '03) SITA WASTECARE LTD 3a SPENCER TRADING ESTATE The Pickering Rd, DENBIGH, CLWYD, LL16 5TO Fulmer, Buckinghamshire SL3 6HA
Full name and address of local representative (if any) of licence holder	
Location of site to which this licence relates	LAND OFF LON PARCWR, RUTHIN SJ 123 592
Form of deposit or disposal to which this licence relates	Ruthin WASTE TRANSFER STATION CA Site
Types of waste of which deposit or disposal is authorised and any limitation as to quantity	HOUSEHOLD WASTE AS DEFINED IN SECTION 75(5) OF THE ENVIRONMENTAL PROTECTION ACT 1990 AND THE CONTROLLED WASTE REGULATIONS 1992

This Licence is granted subject to the following conditions:—

SEE ATTACHED COPY OF CONDITIONS A1 - N2

TDC/06

Dated 12 FEBRUARY

19 93 .

(Signed)

CHIEF ENVIRONMENTAL
(Designation) HEALTH OFFICER

THE LICENCE HOLDER SHOULD READ CAREFULLY THE NOTES OVERLEAF.

* Insert name of Waste Disposal Authority.

LICENCE CONDITIONS FOR THE OPERATION OF THE GLYNDWR DISTRICT COUNCIL CIVIC AMENITY SITE AT ION PARCWR, RUTHIN
GRID REF SJ 123 592

A. DEFINITIONS AND NOTES

The following meanings shall apply throughout this licence:-

- A.1 Working Plan shall mean the approved plan submitted by the operator together with the accompanying site plan drawings.
- A.2 Waste Regulation Authority (W.R.A.) shall have the meaning assigned to it in Section 30 (1) of Environmental Protection Act 1990. (mod '03)
- A.2.1 All references to the Waste Regulation Authority (WRA) shall include their successor organisation
- A.3 Duly Authorised Officer shall mean any person authorised in writing by the Waste Regulation Authority pursuant to Section 91 (1) of the Control of Pollution Act 1974 and Section 69 of The Environmental Protection Act 1990.
- A.4 Licence Holder shall mean the person or persons to whom this licence is granted.
- A.5 Bund shall mean a metal or suitably bricked contained area to prevent the escape of liquids and be impermeable to the liquids they are designed to contain.
- A.6 Operating shall mean the receipt, depositing and handling of waste or recyclable materials on site.
- A.7 Site Diary shall mean a daily record of all site operations as required and specified in these licence conditions.
- A.8 Drum Container shall mean any container in which material is stored but such containers having storage capacities less than 10 litres or alternatively greater than 250 litres shall not be regarded as drum containers for the purposes of this licence.
- A.9 COPA shall mean the Control of Pollution Act 1974 as amended.
- A.10 EPA shall mean the Environmental Protection Act 1990.
- A.11 Environmental Hazard shall have the meaning contained in Section 4 (5) of the Control of Pollution Act 1974.
- A.12 A Proficient Person shall mean a person trained to understand the terms and conditions of this licence and to recognise the general descriptions of waste that may arrive at the facility. The proficient person shall also know what actions are to be taken to deal with any hazardous wastes deposited on site and those actions to be taken in the event of fire or other such emergencies.

A.13 In this licence "an emergency" shall be defined as a case where a person has reasonable cause to believe that circumstances exist which are likely to endanger life or health or cause damage to property or pollution to water.

A.14 NRA shall mean the National Rivers Authority[^] and ^{their successors,} its ^{their} Officers. (mod '03)

A.15 H & SE shall mean the Health and Safety Executive and its ^{their successors} Officers. (mod '03)

A.16 HMIP shall mean Her Majesty's Inspectorate of Pollution, and ^{their} its Officers. (mod '03)

B. PLANS AND DRAWINGS

B.1 The area which is the subject of this licence is shown outlined in ORANGE on the attached drawing number [789B].

B.2 The deposit and sorting of waste shall take place within the area shaded in BLUE on the attached drawing number [789B].

B.3 The deposit of paper, bottles and clothes shall take place in the relevant containers provided within the area shaded in GREEN on the attached drawing number [789B].

C. OPERATIONAL CONTROL

SITA WASTECARE LTD,
(formerly

C.1 The licence holder will be [^] {BFI WASTECARE LTD} of ^(mod '03) ~~{3A SPENCER TRADING ESTATE, DENBIGH}~~ and whose telephone NO. is ~~[0745 81 4446]~~ and whose registered office is ~~[QUOTRON BUILDING, 5 ROUNDWOOD AVENUE, STOCKLEY PARK, UXBRIDGE, MIDDLESEX, UB11 1BX]~~. The Pickering, Stoke Common Road, Fulmer, Buckinghamshire SL3 6HA

C.2 The licence is to inure for the benefit of the licence holder only.

^(mod '03) C.3 The ~~duly authorised~~ person responsible for the running of the site will be ~~[THE BFI DISTRICT MANAGER]~~ of ~~[3A SPENCER TRADING ESTATE, DENBIGH]~~.

C.4 The conditions of this licence shall be reviewed as necessary or in accordance with the introduction of legislation.

C.5 The Waste Regulation Authority shall be Glyndwr District Council. (ENVIRONMENTAL HEALTH DEPARTMENT).

C.6 The terms and conditions of this licence shall be made ^(mod '03) known to all persons manning or supervising the site, including supervising officers of Glyndwr District Council's Technical and Housing Department, or ^{their successors}

C.7 Subject to the conditions of this licence the site shall be operated in accordance with the approved current working plan.

- C.8 The licence holder shall notify the W.R.A., in writing, at least two months in advance of any proposed change in the approved working plan. Any alterations shall require the prior written consent of the W.R.A. before implementation.

D HOURS OF OPERATION LIGHTING AND EMERGENCY WORK

- D.1 The site shall be operated between the hours of [10.00] to [13.00], [13.30] to [16.30] and [17.30] to [19.15] Monday to Friday, and [10.00] to [13.00] and [13.30] to [18.15] Saturdays and Sundays weekly, when British Summertime is in operation.
- D.2 When Greenwich Mean Time is in operation, the operating hours for the site shall be from [10.00] to [13.00] and [13.30] to [16.00] every day weekly.
- D.3 In this licence hereafter these operating hours shall be assigned the terms "winter hours" for GMT hours and "summer hours" for BST hours of operation. These operating hours as specified in conditions D.1 and D.2 during which the site is permitted to operate shall also be termed the "working day" for the purposes of this licence.
- D.4 With the exception of condition D.7 below, no waste shall be deposited at the "site" outside the "working day".
- D.5 The site shall be closed during Christmas Day, Boxing Day and New Year's Day unless written application is made to, and subsequently approved in writing by the WRA.
- D.6 No waste shall be deposited at the site during the hours covered by official lighting up times, as published by the Science and Engineering Research Council (ie. half an hour before sunset to half an hour after sunrise) unless lighting has been provided on site to a specification agreed upon in writing with the WRA.
- D.7 Operations outside those hours as specified in condition D.1, and subject to D.6, shall only be permitted by the W.R.A. if it is ascertained that it is an absolute necessity for the safety of the general public, to prevent danger to life, or is prejudicial to health, or to prevent damage to property, or to prevent pollution of water.
- D.8 The WRA shall be notified in writing by the licensee of any proposal for the cessation of operations for a period greater than three months.
- D.9 The WRA shall be notified in writing and given at least fourteen days notice of any proposals to recommence operations after a cessation longer than 3 months. Written approval of the WRA shall be received before these operations may recommence.

E. TYPES OF WASTE

E.1 The types of waste permitted at this site shall be as follows:

- (a) Household Waste as defined in Section 75 (5) of the E.P.A. 90 and as further described in the Controlled Wastes Regulations 1992.

E.2 None of the following wastes shall be permitted on site for disposal.

- (a) Industrial Waste as defined in Section 75 of the E.P.A. 90 and as further described in Schedule 4 of the Controlled Waste Regulations 1992.

- (b) Commercial Waste as defined in Section 75 of the E.P.A. 90 and as further described in Schedule 3 of the Controlled Wastes Regulations 1992.

- (c) Clinical Wastes as defined in the Controlled Wastes Regulations 1992 containing any of the wastes identified in any of the groups listed in the Health and Safety Code of Practice.

- (d) Hazardous Wastes as defined in the Trans Frontier Shipment of Hazardous Wastes Regulations 1988.

- (e) *(mod '99)* Those wastes which are ~~subject to Section 17 of the Control of Pollution Act 1974 and defined by the Control of Pollution Act (Special Waste Regulations) 1980.~~ The only exception being chlorofluoro- carbons within the cooling systems of fridges and freezers and within aerosol containers under one litre capacity. *defined by the Regulations in force under Section 62 of the Environmental Protection Act 1990.*

- (f) Waste which is likely to give rise to an Environmental Hazard as referred to in Section 3(3)b and 4(5) of the Control of Pollution Act 1974.

- (g) Agricultural waste.

- (h) Wastes that are within the Control of Radioactive Substances Act 1960 and subsequent amendments.

- (i) *(mod '99)* Asbestos as defined by the ~~Special Waste Regulations, 1980.~~ *in force under Section 62 of the Environmental Protection Act 1990*

- (j) Waste being or including any pressurised gas or liquefied gas or gas dissolved under pressure with the exception of substances within the cooling system of domestic refrigerators and freezers and aerosol containers from domestic premises under one litre capacity.

- (k) Percussives and explosives and other substances with similar characteristics.

- (l) Waste materials which, (either by themselves or in conjunction with any other materials already deposited) are likely to give rise to the combustion of waste materials or to dangerous fumes or gases.
- (m) Liquid Waste.
- (n) Animal carcasses and offal or any waste containing Viable Pathogenic Organisms.
- (o) Organo Halogen (which includes polyhalogenated biphenyls, terphenyls and naphthalenes), organophosphorous, organosulphur, organosilicon and organometallic compounds and substances which may form such compounds on deposit. The only exceptions are for substances within the cooling systems of domestic refrigerators and freezers and aerosol containers under one litre capacity.
- (p) Waste which possess carcinogenic, mutagenic or teratogenic properties.
- (q) Mercury and cadmium compounds.
- (r) Cyanides and sulphide compounds.
- (s) Ammonia, fluoride and nitrite compounds.
- (t) Substances which have a deleterious effect on the taste and/or odour of groundwater and surface waters and compounds liable to cause the formation of such substances in such water and to render it unfit for human consumption eg. Phenols, analogues and their derivatives.
- (u) List I and II substances as defined by the E.C. Groundwater Directive.

F. INFORMATION FOR DISPLAY PURPOSES

F.1 At the site entrance two site identification boards of minimum size 1m x 1m, of durable material and finish shall be displayed in accordance with the approved Working Plan. One board shall bear the following information in English, the other in Welsh.

- a) Site name and licence number
- b) Hours of operation
- c) Name and address and telephone number of the site operator and of the WRA responsible for issuing the licence.
- d) Name, address and telephone number of person to be contacted in an emergency.
- e) The types of waste permitted.
- f) It shall also display the words "NO UNAUTHORISED ACCESS".
- g) Smoking is prohibited within the site.

- F.2 As a supplement to the notices required by condition F1, bilingual signs should also be displayed at the site entrance stating deposits outside the site are a breach of The Environmental Protection Act 1990.
- F.3 Movable bilingual signs to tell members of the public that the site is temporarily out of use until (time & date) due to servicing and maintenance and giving details of the nearest other civic amenity site available, shall be displayed when necessary.
- F.4 Clearly conspicuous and legible bilingual signs shall be provided within the site to indicate:-
- a) The types of wastes to be deposited within specific containers.
 - b) Smoking is prohibited except within the site welfare office.
 - c) Other site management signs as may be required for the satisfactory operation of the site e.g. traffic control signs, no entry, one way, no parking etc.
- F.5 Copies of the approved working plan and site licence shall be displayed at the site control office.
- F.6 Emergency provisions and instructions shall be established and displayed at the site control office, dealing with the following and a copy forwarded to the WRA.
- a) An outbreak of fire on the site.
 - b) The deposit of prohibited waste on the site.

G. SITE CONTROL OFFICE AND WELFARE FACILITIES

- G.1 A site control office shall be provided on site and be maintained in a good state of repair.
- G.2 Welfare facilities shall be available adjacent to the site and shall include suitable water supply, toilet, wash basin. Two way communications shall be available for use at all times when operatives are on site.

H. SITE RECORDS

- H.1 A site diary shall be kept at the site control office and a duplicate taken weekly and kept at the licence holder's registered office. The following data shall be recorded in the diary:
- a) Details of fires
 - b) Details of inspections of security
 - c) Details of inspections for infestations
 - d) Details of inspections of fire fighting equipment
 - e) Details of inspections of WRA, supervising Officer
 - f) Details of inspections by any other authorised persons(s)
 - g) Details of monitoring results

- h) Details of any waste rejected as being unsuitable for disposal at the site, the vehicle type, colour, registration, company name, driver's name, time and date of delivery and carriers registered number, if possible.
- i) All other emergencies
- j) Any other information required by any other condition of this licence
- k) Details of inspections of plant and equipment
- l) As identified in paragraph 8.9 of the approved operating plan all details of all accidents no matter how minor shall be recorded.

H.2 All waste shall be visually inspected on arrival or on deposition to ensure compliance with conditions E1 and E2 of this licence. Waste which does not conform to the said condition E1 shall be rejected as being unsuitable for disposal at this site and removed from the site immediately by the 'depositor', and he shall be advised to contact the WRA to arrange for suitable disposal.

H.3 A separate record shall be kept for all consignments of waste leaving the site.

Details to be recorded shall be

- a) Registration number of vehicle
- b) Drivers and operators names
- c) Types and quantities of waste removed
- d) Time of removal
- e) Carriers registration number
- f) All relevant details shall be recorded on waste transfer notes to comply with all aspects of Section 34 of the E.P.A. 90, ie. The Duty of Care.
- g) Address of the licenced disposal facility the waste is to be removed to.

(mod '99)

H.3.1 See final page of licence

H.3.2 See final page of licence

H.4 No waste shall be removed from the site by any persons except "registered carriers" authorised and registered under the Controlled Waste (Registration of Carriers and Seizure of Vehicles) Regulations 1991.

H.5 Summaries of the records kept by virtue of conditions H1 and H3 of this licence shall be forwarded to the WRA at calendar monthly intervals, to be received at the WRA's office within ten days of the end of each calendar month.

(mod '99)

I. MANNING LEVELS AND SUPERVISION

I.1 When open for operation the site shall be manned by at least 1 operator and supervised and operated in accordance with the approved working plan.

I.2 The name, address and telephone number of the district manager identified in the working plan responsible for overseeing site operations shall be forwarded in writing to the Waste Regulation Authority. Any changes to the information above shall be also forwarded in writing to the Waste Regulation Authority as and when this arises.

I.3 Nominated persons shall be responsible for:

- a) Record keeping
- b) Site security
- c) Site safety
- d) Inspections of plant and equipment
- e) Site operations
- f) De-infestation inspections
- g) Reception and issuing of notices Waste Transfer including - Section 17 of COPA
- h) Operators of on-site plant and equipment

The names of these persons shall be published in the site control offices and a copy forwarded to the WRA for approval before the issuing of this licence. Any change in nominated personnel must be agreed in writing with the WRA beforehand.

J. SITE PREPARATION AND SECURITY

J.1 Access to the site from the public highway shall be solely from the accessway identified on the attached drawing number [789B] of the working plan and as described in the approved working plan. This accessway shall be maintained at all times to the satisfaction of the WRA and County Highway Authority.

(mod'n) J.2 The site accessway referred to in condition J1 in so far as it relates to land within the ownership of Glyndwr or land which Glyndwr has legal control over shall be maintained in good repair. All cracks, erosion or potholes shall be repaired within 7 working days to ensure compliance with the approved working plan statements and drawings. Details of all such repairs shall be recorded in the site diary.

J.3 The primary site access road shall be kept free of mud, stones, wastes or any other debris from the site or deposited by vehicles coming to the site. Where it can be demonstrated that the deposits are attributable to the works carried out at adjacent landfills, the necessary remedial action required by condition J4 shall be carried out by the landfill operators or their agents, under the instructions of and to the satisfaction of the licence holder or the WRA.

J.4 The deposit of any of the material mentioned in condition J3 outside the site gates or onto the public highway adjoining the site shall be treated as an emergency. Immediate effective action shall be taken to remove these deposits including the use of a mechanical sweeper if deemed necessary. Details of all such emergencies and the action taken shall be recorded in the site diary.

J.5 The site entrance shall be provided with access gates capable of being securely locked to BS 1722 part 1, 1986, to a minimum height of 2.0 metres, as specified on drawing number [789B] of the approved operational plan and in the accompanying statements.

J.6 The gates provided by virtue of condition J5 above shall be secured by a sturdy 3" padlock and kept locked shut at all times that the site is unattended for any reason and at all times outside the working day.

J.7 (mod'ed) Where access to landfills is gained through the licenced area, gates to the landfills shall be provided to BS 1722 standards and kept securely locked at all times except during authorised visits, to the landfill operations, or inspections carried out by either Waste Disposal Authority, their agents or officers of WRA, NRA, HMIP or H&SE. ~~their successors.~~

~~Keys to all locks shall be retained by:-~~

- ~~a) The licence holder~~
- ~~b) The WRA~~
- ~~c) The Waste Disposal Authority~~

J.8 The licenced area shall be enclosed by a boundary fence to a minimum standard of BS 1722 to minimum height of 2.0m as specified in the approved operational plan and as illustrated on drawing number [789B] of the plan.

The boundary fences, walls and gates should be of a sufficient standard to prevent unauthorised deposits and unauthorised access occurring on site.

J.9 All gates, locks, boundary walls and fences provided by conditions J5, J6 and J7 of this licence shall be inspected daily. Any damage impairing their effectiveness shall be repaired within two working days.

J.10 All buildings and other structures capable of being closed located within 150 metres of a landfill site shall be fitted with gas alarms. These alarms shall be inspected and tested by competent authorised persons on a regular basis to ensure they are maintained in good working order. Any defects to impair their effectiveness which are discovered shall be repaired within one working day. Details of inspections and repairs shall be recorded in the site diary.

K. SITE DRAINAGE BASE AND OVERHEAD SERVICES

K.1 No deposits of waste shall take place until off-site drainage to intercept and divert surface water run-off from surrounding areas has been provided, to the satisfaction of the WRA and NRA. These facilities shall be inspected once weekly and any blockage or damage impairing their efficiency shall be repaired within three working days. All interceptor systems to be emptied twice annually as a minimum or as per the manufacturers instructions. Emptying to be undertaken by a registered carrier and tank contents disposed of at an appropriate licenced facility. Details of all inspections and repairs shall be recorded in the site diary.

K.2

The area forming the base of the site shall be of the materials and to the standards submitted in the approved operational plan and illustrated on drawing number [789B]. The base of this site shall be maintained in a good state of repair and inspected for cracks, potholes and erosion on a weekly basis. Any defects discovered shall be repaired within seven working days with materials of an approved specification to restore the base of the site to at least the condition specified in the plan. Details of all inspections and repair frequencies and methods used shall be included in the working plan.

K.3

All on site drainage facilities, including gradients of the base of the site, drains, gullies, interceptors, soakaways, catch pits, etc. shall be installed in accordance with the approved operational plan and illustrated drawing and shall be maintained to the satisfaction of the WRA and NRA. These facilities shall be inspected not less than once weekly, and any damage, blockage or filling which may impair their effectiveness shall be repaired or removed within three working days.

K.4

All floor surfaces at the site shall be maintained in a clean, tidy, non slippery condition by the licence holder. The licence holder shall be responsible for cleaning these surfaces at least daily and the spreading of any necessary cleansing or absorption agents. The licence holder shall also be responsible for the spreading of grit sand or rock salt on site to ensure public safety in times of inclement weather.

K.5

All overhead services crossing the site which come within 33% of the maximum elevation of any equipment used on site shall be diverted around the perimeter of the site. Where overhead services cross the site in excess of 33% above the maximum elevated height of any plant or equipment used on site 'goal posts' shall be provided at the site boundaries where the services cross them, to a minimum height of 33% above the maximum elevated plant or equipment used on site.

L.

STORAGE OF LIQUIDS

L.1

No liquids are to be stored on site unless a licence modification is applied for and approved by the WRA.

M.

SITE OPERATIONS

M.1

All fridges deposited on site shall be placed in a specific high sided container within this site solely used for this purpose, pending removal to a suitably licenced site. This container shall be capable of being locked shut and shall be locked at the end of every working day. A sturdy lock of approved BS construction and approved by the WRA shall be used.

M.2

a) Fridges and freezers etc. shall not be multiple stacked whilst awaiting removal offsite they shall only be stored as a single layer. All reasonable care shall be used to prevent damage to the cooling systems of the above items of waste whilst being stored or handled on site.

- b) All locks on fridges and freezers shall be destroyed to ensure that they cannot securely close, entrapping any child.

M.3 All waste accepted for disposal on site shall be deposited only in the containers specified in the approved working plan for this purpose. No waste shall be deposited onto the floor of the site, other than fridges and freezers immediately prior to their removal to other suitably licenced sites or storage in container specified in M1 above.

M.4 All Council recyclable material accepted on site for recycling, shall be deposited only in the containers provided for this purpose, as specified in the approved operational plan.

M.5 FIRE PRECAUTIONS

M.5 a) No materials shall be burnt on site. Any outbreak of fire shall be treated as an emergency and immediate action taken to extinguish it. All outbreaks of fire shall be notified immediately to the WRA and confirmed in writing within 3 days.

b) Bilingual signs shall be displayed bearing the legend "NO SMOKING/DIM YSMYGU" and the site shall be designated a no smoking zone. No materials which are likely to give rise to the combustion of waste shall be deposited on site.

c) Fire fighting equipment and fire precautions shall be implemented in accordance with the Chief Fire Officer's recommendations. The licence holder shall display emergency procedures for dealing with fire, in the site control office and shall make all persons manning the site fully aware of the said procedure. A copy of this procedure shall be forwarded to the WRA prior to issuing this licence.

M.6 LITTER AND LOOSE REFUSE

M.6 a) At the end of every working day all loose waste and windblown litter which may be lying around the site or against its boundaries shall be gathered and disposed of in such a manner as to maintain the site in a tidy condition.

b) No windblown litter shall be permitted to leave the site, any windblown litter leaving the site shall be treated as an emergency and immediate steps shall be taken to gather all windblown litter which has left the site. Details of all such emergencies shall be recorded in the site diary.

c) All containers shall be progressively sheeted/netted to prevent windblown litter leaving the site.

M.7 VERMIN AND INFESTATIONS

- M.7 a) The licence holder shall be responsible for ensuring that the site is inspected at least once a week for infestation by insects and vermin. De-infestation methods shall be applied as necessary. Records of dates of inspection, de-infestation methods applied and notification to the Authority under Section 3 of the Prevention of Damage by Pests Act 1949 are to be kept in the site diary.
- b) Enclosed permanent baiting points for rodents, secure from interference by birds, wildlife and children shall be placed at suitable intervals around the perimeter walls of the site.
- c) Skips and wastes shall be sprayed as necessary to prevent infestation with flies.

M.8 CONTAINERS AND TIPPING OPERATIONS

- M.8 a) No emergency tipping area shall be provided on site. If all containers for the disposal of waste become full to capacity the site shall close and customers shall be directed to the nearest appropriately licenced facility.
- b) All containers provided for the disposal of waste shall only be deposited at the locations stated in the approved operational plan and as illustrated in the submitted drawing number [789B] within the area of site draining to the interceptor system. No container outside the interceptor system to be used for collection of waste to prevent risk of contamination to surface water drainage system. They shall be of type and size as specified in the approved operational plan.
- c) All containers shall allow safe and easy access for vehicles and pedestrians using the site. Precautions shall be taken to exclude the public from the site when the operators of vehicles, plant and equipment are working on the site or when containers are being emptied or replaced.
- d) All containers which contain putrescible or other waste likely to give rise to a public health hazard shall be progressively sheeted during filling. Once full they shall be completely and securely sheeted and removed for disposal as soon as practicable. Containers containing the waste must be removed for disposal within i) 72 hours of the deposit occurring if it occurs on Christmas and New Year's Eve and ii) on all other occasions within 48 hours.
- e) All other containers shall be removed for disposal in accordance with the specification of the contract which exists between the licence holder and the Waste Disposal Authority.

- f) When containers are to be transported along the highway to the disposal point, they shall be sheeted or netted down prior to leaving the site in order to avoid spillages of litter and waste and thereby breaches of the Duty of Care.

M.9 REJECTED AND UNAUTHORISED LOADS

- a) If the use of the site results in unauthorised deposits of waste, the WRA shall be notified forthwith. Any such deposits shall be removed in accordance with any directions of the WRA to a disposal point authorised by the WRA along with the necessary waste transfer notices, or COPA Section 17 Notifications.
- b) The WRA shall be informed of the discovery on site of any waste which is rejected as being unsuitable for disposal on site by virtue of condition E2 of this licence. Such waste shall be stored and/or disposed of in accordance with the WRA's instructions and all shipments leaving the site shall be accompanied by the necessary documentation including required under Section 17 COPA 1974 and/or Section 34 EPA 90 as necessary.

M.10 SORTING OF WASTE

- a) The sorting of waste at the site shall only be permitted as part of a properly organised recycling scheme as submitted in a working plan after its subsequent approval.
- b) No persons other than the licence holder, shall extract waste from the site without the prior written approval of the WRA, except those registered carriers under fixed contract for removal of the containers containing waste, or a specifically authorised carrier engaged by contract to remove waste by virtue of condition M9(b).

M.11 PLANT AND EQUIPMENT

- M.11 All plant and equipment to be used on site shall be operated only in accordance with procedures laid down in an approved working plan. All plant and equipment to be operated on site shall be inspected at weekly intervals by a suitably experienced, authorised and competent person. Any defects likely to impair effectiveness or safety shall be recorded in the site diary together with dates and times of inspections.

N. NUISANCES

- N.1 No nuisance shall be caused to nearby occupiers or other users of land as a result of operations on site by reason of atmospheric or airborne pollution or by nuisances which shall include noise, vibration, smoke, smell, fumes and dust, ash, soot, grit, light dazzle, windblown papers and television and radio interference.

N.2


All reasonable measures including proper maintenance and use shall be undertaken to control the noise of machinery and vehicles operating at the facility to ensure it is not seriously detrimental to the amenities of the locality.

- (mod '99) H.3.1 A record shall be kept of all wastes received (other than those wastes delivered by private households) and of all materials (wastes and recovered materials) removed from the site. The records shall include the following for each vehicle load of waste/material.
- For waste received:
- b) Origin of Waste
 - c) Date received
 - d) Quantities in tonnes received and waste type as specified in Condition No. E.1 and E.2
 - e) Nature of the waste (solid, liquid or sludge)
- For waste/materials removed
- b) Date removed
 - c) Quantities in tonnes removed and waste and/or material type
 - d) Destination of waste and/or materials removed
 - e) Nature of the waste and/or materials (solid, liquid or sludge)

H.3.2

(mod '99)

A summary of the information, including nil returns shall be submitted to the Agency, in a format required by the Agency. Summaries shall be for each quarter of the financial year and shall be submitted to the Agency within one month of the end of each quarter.



DRAWING No: 789B

C.A. SITE - LON PARCWR, RUTHIN

Disposal Site.

