

# 593 Central Quay, Cardiff - Softworks Schedule

## 593-CTF-XX-XX-SH-L-SW01

General Notes:

Mulching

All planting beds, are to be mulched with 75mm depth ornamental grade bark mulch. Mulch to be 3 - 35mm particle size, less than 5% wood content, minimal dust and fines. Ph 4.5 - 5.5. Sourced from Pine, Douglas Fir. Where planting beds are to be mulched finished level of topsoil to allow for future installation of nominal 75mm deep layer of bark mulch. All finished mulch levels to be below damp proof course where applicable.

Planting Stock

All plants to be a full and well formed example of its type, with fully established roots having been grown in the specified container for at least a full season. Landscape Contractor to approve any cutting back of flowering plant stock to comply with BS 3936 'Nursery stock specification for trees and shrubs'. Handling of plants to be undertaken according to The Horticultural Trades Association (HTA) National Plant Specification (including Appendix 1, 2 and 3). To also comply with the Landscape Institute and HTA guidance: The Committee for Plant Handling and Establishment Part 3 - 'Recommendations for Plant Handling from Delivery to Successful Establishment'.

All plants to be delivered on racks. Boxed / pallet stacked plants are not acceptable. To assist the on site setting-out each rack must contain a labelled plant that is a representative sample of the species.  
Contractor to ensure that all planting areas are free draining, not compacted and suitable for the future planting requirements.  
Landscape Architect to select and tag trees from nursery stock, suggested tree and plant stock suppliers are to be used as a guide only.

Calculations

All calculations of trees, planting numbers and areas are provided as an guide only, all areas and numbers to be checked and calculated by a suitably qualified quantity survey or cost consultant. Any errors should be highlighted and the landscape architect notified.

Setting out of Planting

The setting out and layout of perennials and shrub planting is to be supervised by a qualified Landscape Architect to ensure a satisfactory finish is achieved due to the nature of a naturalistic planting style. Landscape Architect to be notified at least two weeks prior to planting is set out.

Revision Tracker

Status

Date

P01 - Issued for costing

D1

To be read in conjunction with Planting Plan Drg No. 593-CTF-XX-GF-DR-L-5001/5002/5003/5004

Bristol  
1.14 Temple Studios,  
Temple Gate, BS1 6QA

+44(0)20 3727 6788  
mail@churchmanla.co.uk

593 Central Quay - Softworks Schedule  
PL-01 - Riverbank planting

Total Area m2 **TBC**

[illegible]

## 593 Central Quay - Softworks Schedule

### PL-02 Riverbank SuDS planting

Total Area m2 TBC

[illegible]